

Technical Information Service 34/17 ENU AH03

AH03 - Replacing Passenger Airbag Unit (Recall Campaign)

Model Line: 718

Model Year: 2017

Subject: Passenger's airbag unit

Information: There is a possibility that passenger airbags with incorrect detonator units were installed as a

result of a supplier's manufacturing error.

In the event of accidents in which the restraint systems are triggered, their full protective effect may be

impaired as a result.

Remedial

Action:

Replace passenger airbag unit.

Affected Vehicles:

Only the vehicles assigned to the campaign (see also PIWIS Vehicle information). This campaign affects

132 vehicles in North America.

Parts required

Important: NOTE: PARTS WILL NOT BE AUTOMATICALLY ALLOCATED TO YOUR DEALERSHIP. ALL PARTS

MUST BE ORDERED VIA A PTEC/PAV.

Parts Info: Part No. Designation Qty.

Use

 $000\,043\,210\,80$ \Rightarrow Airbag unit, passenger's side 1 ea.

N 911 859 01 \Rightarrow Fastening screw 2 ea.

- Airbag unit on passenger's side

Also required for vehicles with knee airbag for passenger's side (I-no. 560):

999 919 278 01 \Rightarrow Hexagon round-head bolt 2 ea.

- For securing knee airbag

Required tools

Tools: • Torque wrench, 2 - 10 Nm (1.5 - 7.5 ftlb.), e.g. **V.A.G 1783 - Torque wrench, 2-10 Nm (1.5-7.5**

ftlb.) or equivalent

Torque wrench, 6 - 50 Nm (4.5 - 37 ftlb.), e.g. V.A.G 1331 - Torque wrench, 6-50 Nm (4.5-37


ftlb.)or equivalent

Service

AH03 ENU 34/17

Replacing passenger airbag unit

Overview:



Installation position of passenger's airbag unit

WARNING

Incorrect handling of airbag units

- Triggering of airbag unit.
- · System faults can occur.
- ⇒ Switch off ignition and remove ignition key or remote control (hand-held transmitter).
- ⇒ A voltage supply (e.g. battery charger) must not be connected to the external power supply/jump-lead starting terminals.
- ⇒ Disconnect the battery and insulate the ground strap so that all contact with a ground carrier is avoided.
- ⇒ Wait 1 minute after disconnecting the battery.
- ⇒ Only pull off connector on the triggering unit after the waiting time has elapsed.
- ⇒ Make sure that no foreign objects are located in front of the airbag unit during installation.

Technical Information

Service

34/17 ENU AHO3

6

- ⇒ Replace damaged parts during removal.
- ⇒ Always position airbag units so that the blow-out opening is facing upwards, e.g. crest on driver's airbag.
- ⇒ Do not position anything on the airbag units.
- ⇒ If removed for an extended period, the airbag units must be stored in a safe place.
- ⇒ Airbag units must not come into contact with grease, oil, detergents, liquids, or similar substances.
- ⇒ Do not expose airbag units to temperatures above 194° F (90° C).
- ⇒ Do not remove the short-circuit spring on the plug-in contacts.
- ⇒ Ignition and preparations may only be carried out by skilled staff, supervised by a second responsible person.
- ⇒ Before disposal, the airbag unit must be rendered harmless by electrical ignition performed in accordance with all precautionary measures, thereby preventing it from being used incorrectly.

Work Procedure: 1 Disconnect the battery \Rightarrow Workshop Manual '2XOOIN Work instructions after disconnecting the battery'.

2 Replace passenger airbag unit. For instructions, see: *⇒ Workshop Manual '695919 Removing and installing passenger's airbag unit'*.



Information

Replaced airbag units must be retained by the Porsche dealership and must not be handed over to the customer (the customer has no right to keep them).

Replaced airbag units must be returned to the **facing PDC** in the **original packaging** used for shipping the spare part due to possible recourse claims (against the parts manufacturer or supplier). Make sure that the **original packaging is not damaged when unpacking the spare part** so that it can be re-used for returning the removed parts.

- Connect the battery \Rightarrow Workshop Manual '2X00IN Work instructions after disconnecting the battery'.
- 4 Enter passenger airbag unit replacement and the campaign in the Warranty and Maintenance booklet.

Service AH03 ENU 34/17

Technical Information

Labor time: 84 TU

Warranty processing



Information

The working times specified were determined especially for the performance of this campaign and may deviate from the working times published in the catalog of operations contained in PIWIS.

Scope 1: Vehicles without knee airbag on passenger's side

Working time:

Replacing passenger airbag unit

Includes: Disconnecting and connecting the battery

Removing and installing glove compartment Removing and installing cover for center console

Removing and installing cupholder

Removing and installing dashboard cover on passenger's

side

Removing and installing footwell light

Removing and installing multimedia interface Removing and installing dashboard moulding on

passenger's side

Parts required:

 000 043 210 80
 Airbag unit, passenger's side
 1 ea.

 N 911 859 01
 Fastening screw
 2 ea.

⇒ Damage Code AH03 099 000 2

Technical Information

Service

34/17 ENU AHO3

6

Labor time: 89 TU

Scope 2: Vehicles with knee airbag on passenger's side (I-no. 560)

Working time:

Includes:

Replacing passenger airbag unit

Disconnecting and connecting the battery

Removing and installing glove compartment Removing and installing cover for center console

Removing and installing cupholder

Removing and installing dashboard cover on passenger's

side

Removing and installing footwell light

Removing and installing multimedia interface Removing and installing dashboard moulding on

passenger's side

Removing and installing knee airbag on passenger's side

Parts required:

000 043 210 80 Airbag unit, passenger's side

1 ea.

N 911 859 01

Fastening screw

2 ea.

999 919 278 01

Hexagon round-head bolt

2 ea.

⇒ Damage Code AH03 099 000 2

Important Notice: Technical Bulletins issued by Porsche Cars North America, Inc. are intended only for use by professional automotive technicians who have attended Porsche service training courses. They are written to inform those technicians of conditions that may occur on some Porsche vehicles, or to provide information that could assist in the proper servicing of a vehicle. Porsche special tools may be necessary in order to perform certain operations identified in these bulletins. Use of tools and procedures other than those Porsche recommends in these bulletins may be detrimental to the safe operation of your vehicle, and may endanger the people working on it. Properly trained Porsche technicians have the equipment, tools, safety instructions, and know-how to do the job properly and safely. If a particular condition is described, do not assume that the bulletin applies to your vehicle, or that your vehicle will have that condition. See your authorized Porsche Dealer for the latest information about whether a particular technical bulletin applies to your vehicle. Part numbers listed in these bulletins are for reference only. Always check with your authorized Porsche dealer to verify the current and correct part numbers. The work procedures updated electronically in the Porsche PIWIS diagnostic and testing device take precedence and, in the event of a discrepancy, the work procedures in the PIWIS

Tester are the ones that must be followed.

Dealership	Service Manager	 Shop Foreman	 Service Technician	 	
Distribution			0		
Routing	Asst. Manager	 Warranty Admin.	 Service Technician	 	

Dr. Ing. h.c. F. Porsche AG is the owner of numerous trademarks, both registered and unregistered, including without limitation the Porsche Crest®, Porsche®, Boxster®, Carrera®, Cayenne®, Cayenne®, Macan®, Panamera®, Speedster®, Spyder®, Tiptronic®, VarioCam®, PCM®, PDK®, 911®, RS®, 4S®, 718®, 918 Spyder®, FOUR UNCOMPROMISED®, and the model numbers and distinctive shapes of the Porsche automobiles such as, the federally registered 911 and Boxster automobiles. The third party trademarks contained herein are the properties of their respective owners. Porsche Cars North America, Inc. believes the specifications to be correct at the time of printing. However, specifications, standard equipment and options are subject to change without notice. Some options may be unavailable when a car is built. Some vehicles may be shown with non-U.S. equipment. Please ask your authorized Porsche dealer for advice concerning the current availability of options and verify the optional equipment that you ordered. Porsche recommends seat belt usage and observance of traffic laws at all times.