

Bulletin No.: PIT5184A

Date: Nov-2013

PRELIMINARY INFORMATION

Subject: Various Concerns Related To The IP Backlighting, Cruise Control, Steering Wheel Controls, Horn

Models: 2007-2014 Cadillac Escalade Models

2007-2013 Chevrolet Avalanche, Silverado, Suburban, Tahoe

2014 Chevrolet Silverado 2500 / 3500, Suburban, Tahoe

2007-2013 GMC Sierra, Yukon and Denali Models

2014 GMC Sierra 2500 / 3500, Yukon Models

This PI was superseded to update model list. Please discard PIT5184.


The following diagnosis might be helpful if the vehicle exhibits the symptom(s) described in this PI.

Condition/Concern

Some owners may comment on any of the following issues and the vehicle may have DTC B0835, B3794, and/or B2610 set in the BCM:

- IP backlighting flashes, flickers or inoperative
- Unwanted horn activation
- Radio controls inoperative or unwanted activation
- OnStar unwanted activation
- Cruise control inoperative

Inspect for a short to ground on the steering wheel near the SIR coil connector X2, see picture below. Depending on which circuit is shorted, this will cause any of the various symptoms mentioned above.



Recommendation/Instructions

1

Make necessary repairs to any shorted circuits and then position the wiring so it will no longer make contact with the steering wheel.

Warranty Information

For vehicles repaired under warranty, please use the appropriate warranty labor operation based on the actual cause and repair. The latest version of bulletin 10-00-89-005: "Warranty Administration - Revised Wiring Repair Labor Operations and Required Additional Information" can be used as a reference.

Please follow this diagnostic or repair process thoroughly and complete each step. If the condition exhibited is resolved without completing every step, the remaining steps do not need to be performed.

GM bulletins are intended for use by professional technicians, NOT a "do-it-yourselfer". They are written to inform these technicians of conditions that may occur on some vehicles, or to provide information that could assist in the proper service of a vehicle. Properly trained technicians have the equipment, tools, safety instructions, and know-how to do a job properly and safely. If a condition is described, DO NOT assume that the bulletin applies to your vehicle, or that your vehicle will have that condition. See your GM dealer for information on whether your vehicle may benefit from the information.

WE SUPPORT VOLUNTARY TECHNICIAN CERTIFICATION