



Countries: AUSTRALIA, BRAZIL, CANADA, UNITED STATES, MEXICO, SOUTH AFRICA
Document ID: IK1300085
Availability: ISIS, Bus ISIS, FleetISIS, Body Builder
Revision: 3
Major System: BRAKES
Created: 5/19/2011
Current Language: English
Last Modified: 8/2/2013
Other Languages: NONE
Author: Anthony Kelso
Viewed: 461

[Less Info](#)

Hide Details

Coding Information

Copy Link 	Copy Relative Link 	Bookmark View My Bookmarks	Add to Favorites 	Print 	Provide Feedback 	Helpful 9	Not Helpful 2
----------------------	-------------------------------	--	-----------------------------	------------------	-----------------------------	-------------------------	-----------------------------

Title: Wabco FPB/ Quadraulic Brake Lining Replacement and uneven wear


Applies To: CE, BE, Durastar

DESCRIPTION

During service of FPB Quadraulic Caliper Brake Linings and for uneven lining wear **greater than 1/4"** between inner and outer pad on the same wheel end it is recommended to use OEM material , MA707 or MA708 (based on GVWR / application, see parts by vin), and service **must** include replacement of the wear plates and retainer anti-rattle spring. Clean plate mating surfaces prior to installation.

PARTS INFORMATION

Part #	Description	Qty.
2600687C91	Hardware Kit, Caliper	1 per caliper



Item	Part Number	Description
1	2600687C91	HARDWARE KIT, CALIPER

[Quadraulic Brake Service Manual](#)



Hide Details

Feedback Information

Viewed: 460
Helpful: 9
Not Helpful: 2

No Feedback Found

Copyright © 2013 Navistar, Inc.