

**Tech Tip** L-TT-0127-13

July 29, 2013

Navigation Micro SD Card Error

USA

Audio/Visual/Telematics

2014 IS Models with Navigation

Navigation/Multi Info Display

## **APPLICABLE VEHICLES**

2014

**IS250** 

2014


**IS350** 


## CONDITION

Navigation microSD card reads an error when missing or swapped from another vehicle.



Error message when microSD card is swapped from another vehicle.





MicroSD card installation location.

## RECOMMENDATIONS

- Do not interchange SD cards. Each SD card is "paired" with head unit.
- Once an SD card is paired with a vehicle, it may not be swapped into a different vehicle.
- A new SD card is "unpaired" and becomes "paired" when inserted into a vehicle.
- If an SD card is swapped, returning it to the original vehicle will remedy the problem.

## **LINK REFERENCES**

This Tech Tip does not contain any link references

Expires on

07/29/2014 Rev1

© 2013, Lexus, a Division of Toyota Motor Sales, USA

Page 1 of 1