



NUMBER: 08-014-13

GROUP: Electrical

DATE: March 14, 2013

This bulletin is supplied as technical information only and is not an authorization for repair. No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, or otherwise, without written permission of Chrysler Group LLC.

THIS SERVICE BULLETIN IS ALSO BEING RELEASED AS RAPID RESPONSE TRANSMITTAL (RRT) 13-017. ALL APPLICABLE SOLD AND UN-SOLD RRT VIN'S HAVE BEEN LOADED. TO VERIFY THAT THIS RRT SERVICE ACTION IS APPLICABLE TO THE VEHICLE, USE VIP OR PERFORM A VIN SEARCH IN TECHCONNECT. ALL REPAIRS ARE REIMBURSABLE WITHIN THE PROVISIONS OF WARRANTY.

HELP USING THE wiTECH DIAGNOSTIC APPLICATION FOR FLASHING AN ECU IS AVAILABLE BY SELECTING "HELP" THEN "HELP CONTENTS" AT THE TOP OF THE wiTECH DIAGNOSTIC APPLICATION WINDOW.

THE wiTECH SOFTWARE LEVEL MUST BE AT RELEASE 13.03 OR HIGHER TO PERFORM THIS PROCEDURE.

SUBJECT:

Flash: Approach Lamp Modification

OVERVIEW:

This bulletin involves flash reprogramming the Body Control Module (BCM) with new software.

MODELS:

2013 (LX) Chrysler 300 (Japan Market Only)

NOTE: This Service Bulletin applies to vehicles with Japan Country Code (sales code 8DE) built before January 25, 2013 (MDH 0125XX).

SYMPTOM/CONDITION:

Approach lamps stay on after the vehicle has been started.

DIAGNOSIS:

If a customer's VIN is listed in VIP or your RRT VIN list, perform the repair.

REPAIR PROCEDURE:

NOTE: Install a battery charger to ensure battery voltage does not drop below 13.2 volts. Do not allow the charging voltage to climb above 13.5 volts during the flash process.

NOTE: If this flash process is interrupted/aborted, the flash should be restarted.

1. Reprogram the Body Control Module (BCM) with the latest software. Follow the detailed service procedures available in DealerCONNECT/TECHCONNECT, Refer To 8 - Electrical Control Modules - Standard Procedure > FLASH PROGRAMMING.
2. **After reprogramming**, Clear any DTC's that may have been set in other modules due to reprogramming. The wiTECH application will automatically present all DTCs after the flash and allow the tech to clear them.

POLICY:

Reimbursable within the provisions of the warranty.

TIME ALLOWANCE:

Labor Operation No:	Description	Amount
18-19-02-9J	Module, Body Control Module (BCM) - Reprogram (1-Semi-Skilled)	0.2 Hrs.

FAILURE CODE:

FM	Flash Module
----	--------------