



Bulletin No.: PIC6045

Date: Nov-2014

Service Bulletin

PRELIMINARY INFORMATION

Subject: Front Seat-Mounted Speaker Buzz


Models: 2013 Cadillac XTS
Equipped with RPO UQS

Condition/Concern

Some customers may comment that the speakers on top of the seats make a buzz noise. This concern is most likely to be evident on AM or Talk radio.

Recommendation/Instructions

Verify Service Update 13004 has been performed first, if applicable. If this concern is still present, separate the speaker housing and apply felt tape to the raiser section as shown below.



Parts Information

Part Number	Description	Material Allowance
KT13486*	BRS (Felt Type) Tape, 30mm x 10 feet per roll	\$3.12 per Seat

*There is enough material to do approximately 10 seats per roll. Store the remaining material for future use. For product ordering information, contact Kent Automotive at 1-888-937-5368 or www.kent-automotive.com.

Warranty Information

For vehicles repaired under warranty use:

Labor Operation	Description	Labor Time
7080178*	Separate The Speaker Housing And Apply Felt Tape (One Front Seat)	1.7 hr
Add	Other Front Seat (If Needed)	1.6 hr
* This is an unique labor operation for bulletin use only. This will not be published in the Labor Time Guide.		

GM bulletins are intended for use by professional technicians, NOT a "do-it-yourselfer". They are written to inform these technicians of conditions that may occur on some vehicles, or to provide information that could assist in the proper service of a vehicle. Properly trained technicians have the equipment, tools, safety instructions, and know-how to do a job properly and safely. If a condition is described, DO NOT assume that the bulletin applies to your vehicle, or that your vehicle will have that condition. See your GM dealer for information on whether your vehicle may benefit from the information.



WE SUPPORT VOLUNTARY TECHNICIAN CERTIFICATION