A PDF of this newsletter and previous ones can be found by logging in to ServiceNet and clicking on the Elsa Newsletter section in the Technician References menu.

## VW Elsa Newsletter



Edition 79: March 31, 2014

## Content

- Maintenance Procedures
   Access
- ETKA Integration with ElsaPro
- Technical Bulletins
- Pending Service Solutions
- <u>Tech Tips</u>
- <u>Campaigns</u>
- Updates
- Suggestions



## **Maintenance Procedures Access**

The maintenance procedures under the Repair Manual infomedia in ElsaPro will be moved. Maintenance information will now be accessible through the Maintenance tab located on the Infomedia Toolbar Menu at the top right within ElsaPro. This move is to help take advantage of behind—the-scenes capabilities of ElsaPro.

(See diagram below)



#### Back to top

## ETKA Integration with ElsaPro

The launch of ElsaPro now provides integration with ETKA, allowing a VIN number (or Vehicle Model and Year) to be transferred into the catalog...

- Set up ElsaPro See the latest ElsaPro internet set up instructions on ServiceNet: ServiceNet / Technician References / ElsaPro Job Aids / "ElsaPro/ETKA integration instructions"
- Set up ETKA Open ETKA and go to MAINTENANCE / INI\_Editor / ETKA\_ELSA Check box "Use ELSAPro"
   Fill in the URL address \*

The ELSA icon will now be active in ETKA:




### 3. From ElsaPro

\* The web address at the top of your internet browser when you log in to ElsaPro will show the URL address required for Step #2.

Enter a VIN or perform a Vehicle Identification search by Model and Year.


Click on the ETKA icon in the header to open ETKA and automatically transfer the VIN (or Model and Year information).



#### 4. From ETKA

While using ETKA, you can click on the ELSA icon in the header to maximize a session of ElsaPro that is already open (you cannot open ElsaPro with this icon).

Note: no information can be transferred from ETKA to ElsaPro, there is a one-way transfer from ElsaPro to ETKA.



#### Back to top

## **Technical Bulletins**

01 14 08 - 2014815 Supersedes Technical Bulletin V010901 dated January 08, 2009 due to additional model year applicability.  Gasoline Quality							
Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To		
All except Routan	2000–2014	All	All	All	All		
The use of con	The use of contaminated gasoline, seasonal fuel changes (summer/winter fuel) or						

gasoline with a low content of deposit control additives may result in one or more of the following conditions:

- Excessive accumulation of deposits on intake valves, intake manifold, fuel injectors and combustion chambers.
  - Engine runs rough after cold start.
  - Excessive engine cranking time.
    - Stumbles while driving.
      - Rough engine idle.
    - Loss of engine performance.
      - Poor fuel economy.

Conditions may be severe enough to illuminate the MIL in conjunction with storage in the ECM data memory of DTCs for misfire (example: P0300, P030x) and / or lean fuel system (example: P0171, P0174, P1128, P1130, P1136, P1138).

**Production Solution:** No production change required.

# 15 14 02 · 2032150 Supersedes TB V151203 dated December 20, 2012 to include 2014 model year applicability.

### Proper Removal of Engine Cover to Avoid Breakage

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
All	2009– 2014	2.0L TDI (CBEA, CJAA)	All	All	All

Pulling on the engine cover in some areas can cause damage. **Production Solution:** Not Applicable.

# 23 14 03 · 2036656 Supersedes Technical Bulletin V231402 dated March 7, 2014 to include additional instruction.

## MIL ON, No Start, or Rough Running with DTCs P0087, P0088 or P0191 Stored in ECM Fault Memory (TDI ONLY)

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
All	2009–2014	All with TDI	All	All	All

When diagnosing the condition above on a common rail diesel vehicle, if no root cause is found after checking all other components and all GFF diagnostic

procedures have been performed, it may be necessary to check for metallic particles in the High Pressure Fuel Pump using the service section of this bulletin.

If such an inspection is necessary, the following guidelines must be observed when removing the N290 Fuel Metering Valve.

**Production Solution:** No production change required.

# 60 14 01 · 2019568 Supersedes T.B. V601301 dated June 6, 2013 to include additional model year applicability. Sunroof / Sunshade, Will Not Open

Note: This bulletin is not applicable to Golf/GTI/Golf R, Eos or Routan. DO NOT replace component(s) for this condition.

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
Jetta Wagon	2008– 2009	All	All	All	All
Tiguan	2008– 2014	All	All	All	All
Jetta SportWagen, Golf Wagon	2010– 2014	All	All	All	All
Jetta, Touareg	2011– 2014	All	All	All	All
Passat, Beetle	2012– 2014	All	All	All	All

The panoramic sunroof, regular sunroof or sunshade cannot be opened. The following fault codes (see bulletin) will set in fault memory of control module **4F** 

Panorama roof (Except Touareg, Vehicle Electrical System 2).

Production Solution: Not applicable.

# 69 14 02 - 2029767 Supersedes Technical Bulletin V691301 dated February 11, 2013 to include additional model year applicability.

## Airbag Warning Lamp Illuminated in Instrument Cluster, DTC B101614 Stored in Airbag Control Module

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To	
----------	------	--------------	----------------	-------------------	-----------------	--

Golf, GTI, Jetta SportWagen	2010– 2014	All	All	All	All
Jetta Sedan	2011– 2014	All	All	All	All
Passat	2012– 2014	All	All	All	All

Airbag lamp in instrument cluster may illuminate due to unfastened connector for passenger airbag warning lamp.

**Production Solution:** Information only.

# 87 14 01 - 2005566 Supersedes Technical Bulletin V871301 dated October 29, 2013 to include additional model year applicability and warranty claim type 1SP.

### **HVAC**, Unpleasant Odor

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
All (except Routan)	2000–2015	All	All	All	All

Unpleasant odor is coming from Heating and Ventilation system. Odor mainly occurs after vehicle has been sitting (unused) at least 5 hours and within 20 to 60 seconds after vehicle is first started.

Note: This Bulletin may only be applied as "one time only" for vehicles with the complaint. Any future complaints will be at the expense of the customer.

**Production Solution:** Not applicable.

# 91 14 04 · 2035473 Supersedes Technical Bulletin 91 · 13 · 23 dated November 7, 2013 to provide information regarding the changing of the format (new web version).

## Infotainment Worksheet (U.S. Only)

				*	
Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
All (Except Routan)	2014	All	All	All	All

This bulletin provides instructions and information for completing and submitting the updated web version of the Infotainment Worksheet. Like the previous version, the

Infotainment Worksheet allows more detail to be provided for repairs related to the Infotainment System (radio, navigation, Bluetooth, telephone systems, etc.). The new web version provides an easier approach by which to complete and submit the information.

Because of advanced and frequently changing technology, it is critical that detailed information is provided in order to better understand issues related to Infotainment.

One or more of the following symptoms are possible, but not limited to:

- Poor AM/FM/Satellite radio reception.
  - Poor sound quality.
- Inability/difficult to pair phones, phone loses pairing.
  - Navigation system malfunctions or is inoperative.
    - Car-Net system malfunctions or is inoperative.
  - Rearview Camera malfunctions or is inoperative.
    - Radio or Navigation display issues.
    - Poor sound quality during phone calls.
- CD player/changer malfunctions or is inoperative.
- Voice command(s) malfunctions or is inoperative.

**Production Solution:** Not applicable.

## **Pending Service Solutions**

No new Pending Service Solutions this week.

## **Tech Tips**

No new Tech Tips this week.

## **Campaigns**

No new campaigns this week.

Back to top

## **Updates**

No new updates this week.

## **Suggestions**

Please send comments or suggestions to: <a href="www.workshopinformation@vw.com">www.workshopinformation@vw.com</a>

### Back to top

© 2014 Volkswagen of America, Inc. All rights reserved. Information contained in this document is based on the latest information available at the time of printing and is subject to the copyright and other intellectual property rights of Volkswagen of America, Inc., its affiliated companies and its licensors. All rights are reserved to make changes at any time without notice. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or otherwise, nor may these materials be modified or reposted to other sites, without the prior expressed written permission of the publisher.