

Technical Service Bulletin

17 "Oil minimum warning, add one quart of oil" message appears, but oil level is above minimum

17 14 52 2038119/2 September 2, 2014. Supersedes Technical Service Bulletin Group 17 number 14-51 dated August 18, 2014 for reasons listed below.

Model(s)	Year	VIN Range	Vehicle-Specific Equipment
A6, A7, S4, S5, S5 Cabriolet, Q7, Q5	2011-14	All	3.0 FSI Engine

Condition

REVISION HISTORY		
Revision	Date	Purpose
2	-	Revised Warranty (Corrected labor operations)
1	8/18/2014	Initial publication

- The message "Oil minimum warning, add one quart of oil" appears in the instrument cluster, but the oil level is above the minimum level (when measured with special tool T40178).
- There are no DTCs related to oil level stored in the ECM memory.

Technical Background

The oil level sensor is defective.

Production Solution

Updated oil level sensor.



Technical Service Bulletin

Service

- 1. Use special tool T40178 to verify that the oil level is not below the minimum level:
 - Adjust the tool to 132 (Figure 1).
 - The oil level needs to be above "0" (minimum).




Figure 1. Adjusting the tool.

2. Replace the oil level sensor.

Make sure that the oil level is at **max** (at 13 with T40178) with engine oil at operating temperature.



Do not perform an oil consumption test.



Technical Service Bulletin

Warranty

Claim Type:	Use applicable claim type. If vehicle is outside any warranty, this Technical Service Bulletin is informational only.			
Service Number:	1711			
Damage Code:	0010			
Labor Operations:	Replace oil level sensor (For A6, A7, A8)	1711 1900	90 TU	
	Replace oil level sensor (For A4, A5, Q5)	1711 1900	70 TU	
Diagnostic Time:	GFF	No allowance	0 TU	
	Road test prior to service procedure	No allowance	0 TU	
	Road test after service procedure	0121 0004	10 TU	
	Technical diagnosis at dealer's discretion			
	(Refer to Section 2.2.1.2 and Audi Warranty Online for DADP allowance details)			
Claim Comment:	As per TSB # 2038119/2			

All warranty claims submitted for payment must be in accordance with the *Audi Warranty Policies and Procedures Manual*. Claims are subject to review or audit by Audi Warranty.

Required Parts and Tools

Part number	Part Description	Quantity
03C907660R	Oil level sensor	1

Tool number	Tool Description	
T40178	Oil level measuring tool	

Additional Information

All parts and service references provided in this TSB (2038119) are subject to change and/or removal. Always check with your Parts Department and service manuals for the latest information.