

A PDF of this newsletter and previous ones can be found by logging in to ServiceNet and clicking on the [Elsa Newsletter](#) section in the Technician References menu.

Audi Elsa Newsletter

Edition 70: January 27, 2014

Content

- [Technical Bulletins](#)
- [Pending Service Solutions](#)
- [Campaigns](#)
- [Updates](#)
- [Suggestions](#)



Technical Bulletins

91 Top view camera cannot be calibrated (2036191/1)

Model(s)	Year	Vehicle Specific Equipment
A6, A7, A8, Q7	2013-2014	Top View Camera

Condition: One of the top view cameras will not calibrate.

Production Solution: Not applicable.

17 Dashboard lights may flicker under hard acceleration or when engine is revved (2036194/1)

Model(s)	Year	Vehicle Specific Equipment
S6, S7, S8	2013-2014	Not Applicable
RS7	2014	Not Applicable

R8	2008–2014	Not Applicable
<p>Condition: The dashboard lights and controls may briefly flicker under hard acceleration after downshifting or when the engine is revved while the vehicle is stationary. The issue does not occur during normal driving, and all instrumentation continues to operate correctly.</p> <p>Production Solution: Not applicable.</p>		

90 Head-up display dims or flickers (2036132/1)		
Model(s)	Year	Vehicle Specific Equipment
A6, A7	2012–2014	Technology Package PR-KS1
<p>Condition: Customer may report that the head-up display (HUD) flickers or dims quickly.</p> <p>Production Solution: Optimized software. The new software prevents fast changes in the brightness of the head-up display. It does not affect the screen brightness level relative to ambient light.</p>		

01 MIL on (DTC P0456 or DTC P0442 (EVAP emission control system leak detected)) (2035519/3)		
Model(s)	Year	Vehicle Specific Equipment
Q7	2013–2014	Not Applicable
<p>Condition:</p> <ul style="list-style-type: none"> • MIL on. • One of the following DTCs is stored in the engine control module (ECM), J623 (address word 01): <ul style="list-style-type: none"> ○ DTC P0456 (EVAP Emission Contr. Sys. (very small leak) Leak Detected) ○ DTC P0442 (EVAP Emission Contr. Sys. (small leak) Leak Detected) • Drivability is not affected. <p>Production Solution: Not applicable.</p>		

94 Xenon headlight flickers or is inoperative on one side (DTC 00978 or 00979) (2021751/4)

Model(s)	Year	Vehicle Specific Equipment
A4, Q5	2009	Xenon headlights
A5	2008-2009	Xenon headlights

Condition:

- The xenon headlight on one side of the vehicle flickers or is inoperative. The condition may be intermittent or permanent.
- One of the following DTCs is stored in the electronic central electronics control module, J519, (address word 09) for the affected headlight:
 - DTC 00978 (Left Low Beam Headlight -M29- Electrical fault in circuit).
 - DTC 00979 (Right Low Beam Headlight -M31- Electrical fault in circuit).
- Only xenon bulbs manufactured by Philips are affected.

Production Solution: Improved xenon bulbs in production.

Pending Service Solutions

No new pending service solutions this week.

[Back to top](#)

Campaigns

No new campaigns this week.

[Back to top](#)

Updates

No new updates this week.

[Back to top](#)

Suggestions

Please send comments or suggestions to: aoa.workshopinformation@audi.com

[Back to top](#)

© 2014 Audi of America, Inc. All rights reserved. Information contained in this document is based on the latest information available at the time of printing and is subject to the copyright and other intellectual property rights of Audi of America, Inc., its affiliated companies and its licensors. All rights are reserved to make changes at any time without notice. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or otherwise, nor may these materials be modified or reposted to other sites, without the prior expressed written permission of the publisher.