

2015

Q7/Q7 TDI

Audi Technician Report

Road test mileage in
n Audi technician prevent excessive battery discharge during inspection all 5F Test Plans in GFF and also to ensure SVM sees all control units
FF for the PDI function tests
eference Document posted on ServiceNet for additional information
Trunk Inspection (continued)
☐ Verify operation of retractable luggage cover
$\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ $
Lighting and Windshield Install wiper blades Test exterior lighting functions* Test front washers (and rear/headlight washers if equipped)* Interior Check heated steering wheel operation (if equipped) Verify operation heated/ventilated seats (if equipped)* Verify operation of all seat belts and latches Verify operation of front Passenger Occupant Detection System Verify proper operation of climate control* Verify the glove compartment opens and closes properly
Switches / Outlets and Windows Check horn operation Check operation of window, lock, and seat controls* Check panoramic sunroof operation* Inspect mirrors for proper operation* Inspect operation of all power outlets* Verify operation of all interior lights



2015

Q7/Q7 TDI

Audi Technician Report

Audi connect (USA ONLY) (if equipped)	On-Hoist Inspection (continued)
Check Wi-Fi hotspot functionality*	☐ Set and store tire pressures for either sold vehicle OR stock inventory vehicle (See separate "2015 Normal Load Condition Tire Pressure Table" posted on ServiceNet)*
Connect the dealer demo SIM card to verify system connects to mobile network*	
☐ Enable Google Earth (if equipped)*	Driver Assistance
☐ Turn on the wireless network*	Activate NAV and follow directions back to dealership (if
☐ Verify Audi connect Information Packet is present*	equipped)
	☐ Verify all cruise control functions
Media / Radio / SAT	☐ Verify Audi lane assist functionality (if equipped)
☐ Insert SD card and test function of all slots	☐ Verify Audi side assist functionality (if equipped)
Program the presets to local stations	☐ Verify operation of Audi parking system (if equipped)*
☐ Verify HD Radio is turned "off"*	
☐ Verify operation of AMI	Driving Performance
☐ Verify operation of CD/DVD player (if equipped)	Calibrate rear view mirror*
	☐ Check adaptive air suspension in all positions (if equipped)
Settings	☐ Check for squeaks, rattles and wind noise
☐ Set "Music volume while parking" to 6 lines*	☐ Check steering/tire alignment
Set dealership location in navigation (if equipped)*	☐ Test drive vehicle applying brakes several times*
Set Time source setting to "GPS" and set Auto daylight sav-	☐ Verify engine performance and acceleration*
ings time to "on."*	☐ Verify hold and release of parking brake
☐ Verify and set language and Measurement Units*	☐ Verify quality of radio reception in AM/FM/SAT bands
☐ Verify Voice Activation is operating (if equipped)*	Verify transmission operation, including shift paddles (if equipped)
On-Hoist Inspection	
Check steering, boots, brake system, hoses, tires and wheels for damage	Post-Road Test Inspection Apply Inventory Maintenance Sticker
Check underside of vehicle for fluid leaks and loose compo-	Ensure the yellow tire pressure tag is installed on the steer-
nents	ing wheel
☐ Inspect wheel bolts for proper torque*	Install showroom charger to ensure battery remains charged at all times
Install wheel bolt covers and center caps as supplied*	☐ Interrogate fault memory and print Diagnostic Log
Remove transport suspension blocks (follow ELSA instruction)	Record final mileage and sign checklist
//////////////////////////////////////	sicle has been prepared in accordance with Audi Procedures and
Technician Signature La	ast 8 of VIN Completion Date