



This Field Service Bulletin replaces bulletin FSB 293-024 dated 3.2014.

Date 7.2014 Group 293

No. 026 Release 01

Page 1(3)

SB-10056267-7943
EGR Differential Pressure Sensor MP10 US2007, MP10 US2010

## FSB 293-026, Exhaust Gas Recirculation (EGR) **Differential Pressure Sensor**

(July 2014)

On MACK vehicles equipped with a MACK MP10 engine built between January 1, 2007 and January 1, 2013 that require the replacement of the EGR Venturi tube or an EGR differential pressure sensor, it will be necessary to replace them with a kit to update the system to the current levels.

Note: It is NOT necessary to replace the entire engine harness when a new type sensor is being installed.

Note: Once a vehicle has been updated with the new style EGR venturi tube and differential pressure sensor, future repairs of these components should be performed individually and not with the update kit.


Refer to the appropriate service bulletin in Function Group 29 for service procedures.

PV729-FSB293-026 M USA65468

Group **293** 


No. **026**  Release 01

Page 2(3)



W2088348

Old Style Differential Pressure Sensor



W2079416

New Style Differential Pressure Sensor

Date 7.2014

Group **293** 

No. **026**  Release 01

Page 3(3)

## **Required Parts**

EGR Differential Pressure Sensor Kit	
Description (Application)	Kit Part Number
MP10	22069631

## Kit Includes

Description	Quantity
Sensor	1
Harness	1
Venturi	1
Wrap	1
Screw Sensor	2
Hose Kit	1
O-Ring	1