

Technical Service Bulletin



91 Satellite radio reception complaint; DTC B10F413 (Antenna for satellite radio open circuit)

91 15 77 2039677/1 March 10, 2015.

Model(s)	Year	VIN Range	Vehicle-Specific Equipment
A3	2015 - 2016	All	Not Applicable

Condition

- **DTC B10F413** (Antenna for satellite radio open circuit) is stored in the information electronics control module 1, J794 (address word 5F).
- The customer may have complained about the function of the satellite radio.

Technical Background

The DTC can be incorrectly set in the main unit.

Production Solution

Not applicable.

Service

Follow the most appropriate instructions below.

- If **DTC B10F413** is **sporadic** and the date during which the customer experienced satellite radio reception issues **does not** match the date on which the DTC was set:
Do not perform any repairs. Review TSB 2011500 and share the information with the customer.
- If **DTC B10F413** is **static** and the customer complained about the function of the satellite radio:
This bulletin is not applicable. Continue diagnosis with Guided Fault Finding.
- If **DTC B10F413** is **sporadic**, the date during which the customer experienced satellite radio reception issues **does** match the date on which the DTC was set, and/or the customer saw the message “**ANTENNA: A technical problem occurred. Please contact your Audi dealer**” (Figure 1):
This bulletin is not applicable. Continue diagnosis with Guided Fault Finding.




Figure 1. This error only appears when there is a satellite reception issue and a DTC set at the same time.

Warranty

This TSB is informational only and not applicable to any Audi warranty.

Additional Information

All parts and service references provided in this TSB (2039677) are subject to change and/or removal. Always check with your Parts Department and service manuals for the latest information.