



Engine	Part	Part Number	Quantity
2.0L TFSI: CCTA, CBFA	Oil Filter	06J115403Q	1
	VW 502 00 Use synthetic oil SAE 5W-40, SAE-5W-30, or SAE-0W-40	N/A	4.6L (4.8qt)
	Drain Plug Gasket	N 0138157	1
	Air Filter	1K0129620D	1

Engine	Part	Part Number	Quantity
3.2L VR6: CBRA	Oil Filter	071115562C	1
	VW 502 00 Use synthetic oil SAE 5W-40, SAE-5W-30, or SAE-0W-40	N/A	5.5L (5.8qt)
	Drain Plug + Gasket	N 90813202	1
	Air Filter PR-0Y1,0Y2	1K0129620	1
	Air Filter PR-0Y3	1K0129620B	1

Miscellaneous	Part	Part Number	Quantity
Miscellaneous	Pollen Filter (20K Only)	1K1819653B	1
	Pollen Filter (20K Only)		1
	Driver's Wiper Blade (Left)	8P1955425H	1
	Passenger's Wiper Blade (Right)	8P1955426H	1
	Rear Wiper Blade	8E9955425C	1
	Battery	000915105CCDSP	1
	Battery	000915105DEDSP	1
	Battery	000915105DGDSP	1
Battery	000915105DHDSP	1	

Resetting the service interval display

The dealership performing the service resets the display when the service has been completed. The display is reset as follows:

- Switch the ignition on.

- Pull the knob ⑧ ⇒ *figure 2*. This message appears: **Service due!**




Fig. 2 Overview of the instrument cluster

Pull the knob until the display **Oil change in ----- mi (km)--- days** appears in the display. If the **RESET** button is not pulled within 5 seconds, the display reset mode closes.



Tips

- If a malfunction is present (red symbol), the distance remaining cannot be called up.
- Do not reset the display between service intervals. Doing so will result in an incorrect display.
- If the battery is disconnected, the Service Interval Display values are retained.
- On vehicles with the Driver Information System, you can also call up the service interval display.
- If the service was not performed at the correct time or the service interval display was not reset after service was performed, the additional mileage driven or the elapsed days will be shown as negative numbers.



A3 - 2009 FLUID CAPACITY CHART updated 25 June 2010

Vehicle (Sales Code)	Engine Oil approx. qty. w/filter change	Manual Trans	Auto Trans	Rear Final Drive	Cooling System	Power Steering	Brake System	A/C System	Windshield & Headlight Fluid
A3 FWD (8PA59C) Manual	2.0 TFSI 200 hp (CCTA/CBFA) 4.6L (4.8qt)	6-Spd (02Q) 2.3L (2.4qt) Oil PN G 052 171 A2*	N/A	N/A	8.0L (8.5 qt)***	Electro- Mechanical (No Fluid)	1.0 L (1.1qt) (approximately) Audi Brake Fluid Specification: Use new fluid only. FMVSS 116 DOT 4 or SAE J 1703 Fluid PN B 000 750 *	Refrigerant Use only R134a Refrig. Capacity 525 +/- 25 grams (18.5 ± 0.8 oz.) Refrigerant Oil Use a PAG oil with R134a Oil PN & Capacity 1) For Sanden use 110 cc +/- 10 cc (3.7 ± 0.3 fl. oz.) 2) For Zexel use 120 cc +/- 15 cc (4.1 ± 0.3 fl. oz.) 3) For Denso use 140 cc +/- 10 cc (4.7 ± 0.3 fl. oz.) G 052 300 A2* G 052 154 A2*	5.5L (5.8qt) Fluid PN G 052 164*
A3 FWD (8PA59X) Auto	Audi Oil Spec: VW 502 00** Use synthetic oil SAE 5W-40, SAE 5W-30 or SAE 0W-40	NA	6-Spd DSG (02E) New Fill: 6.9L - 7.2L (7.3qt - 7.6qt) Change: 5.2L (5.5qt) approx.	Capacity included with transmission. Oil PN G 052 182 A2*					
A3 quattro (8PA59L)			6-Spd DSG (02E) New Fill: 6.9L (7.3qt) Change: 5.5L (5.8qt) approx.	0BR 1.0L (1.1 qt) Oil PN G 052 145 A1* Haldex Clutch 0.7L (0.8qt) Oil PN G 055 175 A2*					
A3 S line quattro (8PA51L)	3.2L VR6 250 hp (CBRA) 5.5L (5.8qt) Audi Oil Spec: VW 502 00** Use synthetic oil SAE 5W-40, SAE 5W-30 or SAE 0W-40		Oil PN G 052 182 A2* Bevel Box New Fill: 0.9L (1.0qt) Oil PN G 052 145 S2*	0AV 0.95L (1.0 qt) Oil PN G 052 145 A1* Haldex Clutch New Fill: 0.85L (0.9 qt) Replacement: 0.65L(0.7qt) Oil PN G 055 175 A2*	12.3L (13.0qt)***				

For proper fluid level and filling information, see the Repair Manual and/or Maintenance Manual in ElsaWeb.

*** Oil and fluid part numbers are for reference only. Always check with your Parts Department for the latest part information.**

****Refer to Technical Bulletin 2010043 for engine oils that meet this Audi oil standard.**

***** Audi Coolant Additive Specification and Part Number:** (color is purple) G 12 plus-plus PN- G 012 A8G.