

A PDF of this newsletter and previous ones can be found by logging in to ServiceNet and clicking on the [Elsa Newsletter](#) section in the Technician References menu.

VW Elsa Newsletter



Das Auto.

Edition 126: March 9, 2015

Content

- [Technical Bulletins](#)
- [Pending Service Solutions](#)
- [Tech Tips](#)
- [Campaigns](#)
- [Updates](#)
- [Suggestions](#)



Technical Bulletins

20 15 01 - 2031426 Supersedes T.B. V201307 dated August 14, 2013 to update Tiguan High Pressure Pump Labor Operation Time Units and update part number.

High Pressure Fuel Pump Diagnosis

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
All	2008–2014	2.0L (CCTA, CBFA)	All	All	All

Engine Crank, No Start after Long Periods without Driving. Engine may run rough, and or MIL-ON with DTC P0087-low fuel pressure stored in ECM Fault Memory.

Production Solution: Not Applicable.

27 15 02 - 2033978 Supersedes Technical Bulletin V271301 dated June 13, 2013 to add additional model year applicability.

Generator Replacement

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
All (except Routan, Touareg Hybrid, Jetta Hybrid, eGolf)	2012–2015	All	All	All	All
Charging System inoperative/malfunctions, noise from engine compartment, accessory drive belt damaged or missing. Production Solution: Not applicable.					

64 15 01 - 2039887

Rear Door Glass Inoperative

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
Jetta	1999–2016	All	All	All	All
Passat	1998–2010	All	All	All	All
Tiguan	2009–2016	All	All	All	All
Golf, Jetta Wagon, Jetta SportWagen, Golf Wagon	1999–2014	All	All	All	All
The rear glass cannot be opened / closed, the rear glass may slide down into the door, or the rear glass motor operates but the glass does not move. Production Solution: Not Applicable.					

**87 15 02 - 2037255 Supersedes Technical Bulletin V871406 dated June 19, 2014 to update air distribution box production date.
Whistle Noise from Center Vent Area; Blower Set On 3 or 4 with Full Heat Selected**

Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
Jetta	2013	All	All	All	All
Jetta Hall 84	2014	All	All	AJ_EM350000	AJ_EM426630
Jetta Hall 04	2014	All	All	AJ_EM200001	AJ_EM282126

Customer may hear a high pitched whistle when the Climatic temperature knob is on full heat and the blower is set to either 3 or 4. The temperature flaps allow air to escape past the temperature flap seal.

Production Solution: Introduction of improved air distribution unit CW13/14.

Pending Service Solutions

No new Pending Service Solutions this week.

[Back to top](#)

Tech Tips

**27-15-01 No Crank, No Start After Cold Soak - Date: January 30, 2015
March 6, 2015: Update to Model Year/Information.**

Model(s)	Year	Eng. Code	Trans. Code
Passat, Jetta, Touareg	2014–2015	All	All

Concern may be the result of a leaking vacuum check valve not holding residual pressure overnight. This results in a hard brake pedal that may require more pressure than usual to allow the vehicle to crank. If duplicated, replace the vacuum supply line to the power brake booster, as the check valve is integral to the line.

This will not affect power brake operation while driving.

Campaigns

No new campaigns this week.

[Back to top](#)

Updates

37J5 UPDATE – Connector Wire (NVLW)					
Model(s)	Year	Eng. Code	Trans. Code	VIN Range From	VIN Range To
Golf	2015	1.8T (CXBB)	AQ250	3VW__AU_FM053395	3VW__AU_FM064065
<p>This update has been proactively released to install wire missing in TCM harness during production. The results of this missing wire are that fault code P306B may be set in the background with no MIL ON condition. Additionally, only if an electrical malfunction of the gearbox multi-function switch occurs while the fault code is stored in memory, the gearbox will go into limp mode the next time the vehicle stops.</p> <p style="text-align: center;">This UPDATE is in effect until removed. Vehicle must meet all of the following criteria:</p> <ul style="list-style-type: none">• Procedure is valid only for vehicles that show the 37J5 code in Elsa, Campaign/Action Information screen <u>on the day of repair</u>.• If the vehicle is sold it must be within the NEW VEHICLE LIMITED WARRANTY• Procedure must be performed within the allotted time frame stated in this UPDATE.• Procedure must be performed on applicable vehicles in dealer inventory prior to sale.					

Suggestions

Please send comments or suggestions to: vw.woa.workshopinformation@vw.com

[Back to top](#)

© 2015 Volkswagen of America, Inc. All rights reserved. Information contained in this document is based on the latest information available at the time of printing and is subject to the copyright and other intellectual property rights of Volkswagen of America, Inc., its affiliated companies and its licensors. All rights are reserved to make changes at any time without notice. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or otherwise, nor may these materials be modified or reposted to other sites, without the prior expressed written permission of the publisher.