

Version 1.4

Stock No.	Dealer Number	R.O. No.	
VIN	Road test mileage out	Road test mileage in	
Reminders			
All items must be completed pr	ior to customer delivery by an A	Audi technician	
Audi recommends using an Aud	i approved battery charger to p	prevent excessive battery discharge during inspection	
		FF) only. Do NOT use Guided Functions for any PDI related test the Special functions tab of ODIS Diagnosis for using GFF for PDI	
 It is advised to start ODIS with during the SVM check vehicle co 		ll 5F Test Plans in GFF and also to ensure SVM sees all control unit	
For items marked with *, please	refer to the PDI Technician Ref	ference Document posted on ServiceNet for additional information	
Vehicle Preparation		Trunk Inspection (continued)	
Check Elsa for open campaigns and updates		☐ Verify tool kit is installed securely in luggage compartment	
Deactivate vehicle transport mo	de*	Set spare tire pressure*	
Deactivate air suspension loading mode*		Verify operation of luggage cover	
Set adaption channel to enable CD Ripping (if equipped with NAV)*		Interior	
Set service reminder*		Verify operation of all seat belts and latches	
Perform any open campaigns *		Check operation of window, lock, and seat controls*	
Under the Head Increation		Inspect mirrors for proper operation*	
Under the Hood Inspection	torquo*	Check rear view mirror operation*	
Check battery clamps for proper torque*		Verify operation of all interior lights	
Perform a battery test* Chack and a site of the set and the set of the set o		Check heated steering wheel operation (if equipped)	
Check engine oil level* Check all fluid levels and top off if necessary		Verify operation heated/ventilated & massaging seats (if equipped)*	
Exterior		Verify proper operation of climate control*	
Check all key buttons and features*		Verify rear climate control operation (if equipped)*	
Check all doors for proper powe		Inspect operation of all power outlets*	
	(in equipped)	Check panoramic sunroof operation*	
Lighting and Windshield		Verify operation of front Passenger Occupant Detection	
Test exterior lighting functions		System	
🗌 Install wiper blades		Settings	
Test front washers (and headlight washers if equipped)*		Verify operation of MMI touch pad	
Trunk Inspection		Set Time source setting to "GPS" and set Auto daylight sav- ings time to "on."*	
Verify tailgate is operational		Verify and set language and Measurement Units*	
Install wheel bolt cover removal tool from PDI kit into trunk tool kit*		Verify Voice Activation is operating*	
Effective 9-2-2015-US		PRE-DELIVERY INSPECTION (PDI)	



A7/S7/A7 TDI/RS 7 Audi Pre-Delivery Inspection

Settings (continued)

- Set "Music volume while parking" to 6 lines*
- Set dealership location in navigation (if equipped)*
- □ Load Onboard Video Tutorials*

Media / Radio / SAT

- □ Verify operation of both USB ports
- □ Verify operation of CD/DVD player (if equipped)
- ☐ Insert SD card and test function of all slots
- Program the presets to local stations
- □ Verify HD Radio is turned "off"*

Audi connect (USA ONLY) (if equipped)

- □ Verify Audi connect Information Packet is present*
- □ Connect the dealer demo SIM card to verify system connects to mobile network*
- □ Turn on the wireless network*
- Check Wi-Fi hotspot functionality*
- Enable Google Earth *

On-Hoist Inspection

- Remove hoist access point trim covers (if equipped)*
- Remove transport suspension blocks (follow ELSA instruction)
- Check steering, boots, brake system, hoses, tires and wheels for damage
- Check underside of vehicle for fluid leaks and loose components
- □ Inspect wheel bolts for proper torque*
- □ Install wheel bolt covers*
- Set and store tire pressures for either sold vehicle OR stock inventory vehicle*

Driving Performance

- Check horn operation
- □ Verify hold and release of parking brake
- □ Verify engine Start-Stop System functionality (if equipped)*
- □ Verify engine performance and acceleration*
- Verify transmission operation, including shift paddles (if equipped)
- Test drive vehicle applying brakes several times*
- Check steering/tire alignment
- Check for squeaks, rattles and wind noise
- Check adaptive air suspension in all positions (if equipped)
- 🗌 Verify rear spoiler functionality
- □ Verify quality of radio reception in AM/FM/SiriusXM bands
- Calibrate rear view mirror*

Driver Assistance

- □ Verify cruise control/ACC with Stop & Go functionality (if equipped)
- □ Verify Audi side assist functionality (if equipped)
- □ Verify Audi active lane assist functionality (if equipped)
- Activate NAV and follow directions back to dealership (if equipped)
- Verify all vehicle Head-up Display functionality (if equipped)*
- □ Verify operation of night vision camera (if equipped)
- □ Verify operation of parking system (if equipped)*

Post-Road Test Inspection

- Interrogate fault memory and print Diagnostic Log
- Ensure the yellow tire pressure tag is installed on the steering wheel
- Apply Inventory Maintenance Sticker
- ☐ Install showroom charger to ensure battery remains charged at all times

Technician I certify that all operations have been completed and this vehicle has been prepared in accordance with Audi Procedures and Quality Standards, and has met the standards for Perfect Delivery.				
Technician Signature	Last 8 of VIN	Completion Date	- ' '	



PRE-DELIVERY INSPECTION (PDI) | 2