

#### 2016

### A6/S6/A6 TDI

## Audi Pre-Delivery Inspection

| Stock No. Dealer  | r Number               | R.O. No.   |  |
|---|------------------------|--|--|
| VIN Road test mileage out   |                        | Road test mileage in   |  |
| Reminders   |                        |  |  |
| ► All items must be completed prior to custome  | er delivery by an Audi | technician   |  |
|   |                        | ent excessive battery discharge during inspection                                    |  |
| ► Refer to the Special functions tab of ODIS Dia  | ignosis using GFF for  | the PDI function tests   |  |
| <ul> <li>It is advised to start ODIS with the engine rule during the SVM check vehicle configuration</li> </ul> | nning to enable all 5F | Test Plans in GFF and also to ensure SVM sees all control units                      |  |
| ► For items marked with *, please refer to the P  | 'DI Technician Referer | nce Document posted on ServiceNet for additional information                         |  |
| Vehicle Preparation   | Tr                     | runk Inspection (continued)  |  |
| Check Elsa for open campaigns and updates   |                        | Verify tool kit is installed securely in luggage compartment                         |  |
| ☐ Deactivate vehicle transport mode*  |                        | ]Set spare tire pressure*  |  |
| ☐ Deactivate air suspension loading mode*   | _                      |  |  |
| Set adaption channel to enable CD Ripping (if equipped with NAV)*   |                        | nterior  ] Verify operation of all seat belts and latches                            |  |
| Set service reminder*   |                        | Check operation of window, lock, and seat controls*                                  |  |
| Perform any open campaigns *  |                        | Inspect mirrors for proper operation*  |  |
|   |                        | Check rear view mirror operation*  |  |
| Under the Hood Inspection   |                        | Verify operation of all interior lights  |  |
| Check battery clamps for proper torque*   |                        | Check heated steering wheel operation (if equipped)                                  |  |
| Perform a battery test*   |                        | Verify operation heated/ventilated & massaging seats (if                             |  |
| Check engine oil level*   |                        | equipped)*   |  |
| Check all fluid levels and top off if necessary   |                        | Verify proper operation of climate control*  |  |
| Exterior  |                        | Verify rear climate control operation (if equipped)*                                 |  |
| ☐ Check all key buttons and features*   |                        | Inspect operation of all power outlets*  |  |
|   |                        | Check panoramic sunroof operation*   |  |
| Lighting and Windshield   | _                      | Verify operation of rear side manual sunshades (if equipped)                         |  |
| ☐ Test exterior lighting functions  |                        | Verify operation of power rear sunshade (if equipped)                                |  |
| ☐ Install wiper blades  |                        | Verify operation of front Passenger Occupant Detection System                        |  |
| $\hfill \square$ Test front washers (and headlight washers if   | equipped)*             | System   |  |
| Trunk Inspection  Verify trunk lid is operational  Verify operation of emergency release handle                 |                        | ettings  |  |
|   |                        | Verify operation of MMI touch pad  |  |
|   |                        | Set Time source setting to "GPS" and set Auto daylight sav-                          |  |
| Install wheel bolt cover removal tool from PD   | OT leit into torrela   | ings time to "on."*  |  |
| tool kit*   |                        | Verify and set language and Measurement Units* Verify Voice Activation is operating* |  |

Effective 7-20-2015-US Version 1.3



#### 2016

## A6/S6/A6 TDI

# Audi Pre-Delivery Inspection

| Settings (continued)   | Driving Performance  |
|--|--|
| ☐ Set "Music volume while parking" to 6 lines*   | ☐ Check horn operation   |
| Set dealership location in navigation (if equipped)*   | ☐ Verify hold and release of parking brake   |
| ☐ Load Onboard Video Tutorials*  | ☐ Verify engine Start-Stop System functionality (if equipped)*                                       |
| ☐ Verify Voice Activation is operating*  | ☐ Verify engine performance and acceleration*  |
| Media / Radio / SAT  | <ul><li>Verify transmission operation, including shift paddles (if equipped)</li></ul>               |
| ☐ Verify operation of both USB ports   | ☐ Test drive vehicle applying brakes several times*  |
| ☐ Verify operation of CD/DVD player (if equipped)  | ☐ Check steering/tire alignment  |
| $\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ $   | ☐ Check for squeaks, rattles and wind noise  |
| Program the presets to local stations  | ☐ Check adaptive air suspension in all positions (if equipped)                                       |
| ☐ Verify HD Radio is turned "off"*   | ☐ Verify quality of radio reception in AM/FM/SiriusXM bands  |
| Audi connect (USA ONLY) (if equipped)  | Calibrate rear view mirror*  |
| ☐ Verify Audi connect Information Packet is present*   | Driver Assistance  |
| $\hfill \square$ Connect the dealer demo SIM card to verify system connects to mobile network* | Verify cruise control/ACC with Stop & Go functionality (if equipped)                                 |
| ☐ Turn on the wireless network*  | ☐ Verify Audi side assist functionality (if equipped)  |
| ☐ Check Wi-Fi hotspot functionality*   | ☐ Verify Audi active lane assist functionality (if equipped)   |
| ☐ Enable Google Earth *  | <ul> <li>Activate NAV and follow directions back to dealership (if<br/>equipped)</li> </ul>          |
| On-Hoist Inspection  | ☐ Verify all vehicle Head-up Display functionality (if   |
| Remove transport suspension blocks (follow ELSA instruc  | equipped)*   |
| tion)  | ☐ Verify operation of night vision camera (if equipped)  |
| Check steering, boots, brake system, hoses, tires and wheels for damage                        | ☐ Verify operation of parking system (if equipped)*  |
| Check underside of vehicle for fluid leaks and loose compo-                                    | Post-Road Test Inspection  |
| nents  | ☐ Interrogate fault memory and print Diagnostic Log  |
| ☐ Inspect wheel bolts for proper torque* ☐ Install wheel bolt covers*                          | ☐ Ensure the yellow tire pressure tag is installed on the steering wheel                             |
| $\hfill \Box$<br>Set and store tire pressures for either sold vehicle OR stock                 | Apply Inventory Maintenance Sticker  |
| inventory vehicle*   | Install showroom charger to ensure battery remains<br>charged at all times                           |
| Quality Standards, and has met the standards for Perfect Del                                   | nicle has been prepared in accordance with Audi Procedures and livery.  ast 8 of VIN Completion Date |
| ·///////   | //////   |

Effective 7-20-2015-US Version 1.3