

Subject

Hard Disk Drive (HDD) Replacement Procedure For Gen 7

Market

USA

Service Category

Audio/Visual/Telematics

Section

Navigation/Multi Info Display

Applicability

All Applicable Models

APPLICABLE VEHICLES

2012-2014	Camry	2012-2015	Prius
2012-2014	Avalon	2012-2014	Venza
2013-2014	Avalon HV	2012-2015	Prius PHV
2012-2014	RAV4 EV	2012-2014	Prius V
2013-2015	Land Cruiser	2012-2013	4Runner
2013	Sequoia	2012-2014	Camry HV

CONDITION

When replacing the Hard Disk Drive (HDD) or Navigation Unit (Navi Unit) follow the instructions below:

RECOMMENDATIONS

1. Remove the Navi Unit from the vehicle and replace the HDD or the Navi Unit.
Note: See figures 1 and 2 below for reference.
 - DENSO Exchange part (Navi Unit) is not shipped with HDD
 - DENSO Exchange parts (HDD and Navi Unit) are shipped open for pairing, so these parts should accept the other component.
2. Install the Navi Unit in the vehicle and press the ignition start button once without stepping on the brake pedal (ACC ON). →Screen shows: **“System Loading. Don’t turn off the power.”**
3. After loading completes, the map will be displayed on the screen.
4. Press the ignition start button twice without stepping on the brake pedal (this will switch the vehicle off) and **WAIT FOR SIX MINUTES.**

CAUTION

Skipping step 4 will cause the audio to fail.
 DO NO disconnect the wire harness from the Navi Unit or press the ignition start button during the update process.

- Once the HDD is inserted into the Navi Unit, the HDD has been paired with it.
- Once paired, it cannot be used with any other Navi Unit or other HDD.

Figure 1.





Figure 2.



Subject

Hard Disk Drive (HDD) Replacement Procedure For Gen 7

Market

USA

Applicability

LINK REFERENCES

This Tech Tip does not contain any link references