

Service Bulletin

File in Section:

Bulletin No.: 16-NA-350

Date: October, 2016

TECHNICAL

Subject: Buzz or Rattle Noise from Door Trim Panel


| Brand: Model: | | Model Year: | | VIN: | | Engine: | Transmission: |
|---------------|---------|-------------|------|------|----|---------|---------------|
| Біапи. | wiodei. | from | to | from | to | | |
| Chevrolet | Camaro | 2016 | 2017 | | | All | All |

| Involved Region or Country | North America, Korea, Europe and all N.A. Export Regions | | |
|----------------------------|--|--|--|
| Condition | Some customers may comment on a buzz or rattle type noise coming from the door trim panel. | | |
| Cause | This may be due to speaker vibration caused by high bass. | | |

Correction

If you encounter a vehicle with the above concern, complete the following steps:

1. Remove the affected door trim panel. Refer to Front Side Door Trim Replacement in SI.



- 2. Once the door trim panel is removed, install flocking tape in the 6 locations along the door panel edge as shown above.
- 3. Reinstall the door trim panel and verify the concern is corrected.

Parts Information

BRS Flocking tape is available from Kent Automotive at 1-888-YES-KENT or online at www.kent-automitive.com.

| Description | Part Number | |
|--------------------------|-------------|--|
| BRS Tape (Flocking Tape) | KT 13486 | |

Warranty Information

For vehicles repaired under warranty, use:

| Labor Operation | Description | Labor Time |
|--|--------------------------------------|------------|
| 1080408* | Apply BRS Tape to Door Trim Panel | 0.4 hr |
| Add | Apply to Other Door Trim Panel | 0.3 hr |
| *This is a unique Labor Operation for Bulletin use only. | | |

| Version | 1 |
|----------|---|
| Modified | |

GM bulletins are intended for use by professional technicians, NOT a "do-it-yourselfer". They are written to inform these technicians of conditions that may occur on some vehicles, or to provide information that could assist in the proper service of a vehicle. Properly trained technicians have the equipment, tools, safety instructions, and know-how to do a job properly and safely. If a condition is described, DO NOT assume that the bulletin applies to your vehicle, or that your vehicle will have that condition. See your GM dealer for information on whether your vehicle may benefit from the information.

