#### **Technical Bulletin**



# SERVICE BULLETIN

 Classification:
 Reference:
 Date:

 EL16-017a
 NTB16-039a
 May 31, 2016

## 2015 PATHFINDER WITH 4WD; LOW POWER / STOP LAMPS STAY ON

This bulletin has been amended. The CLAIMS INFORMATION section has been revised.

Please discard all previous versions.

APPLIED VEHICLE: 2015 Pathfinder (R52) 4WD with V6 engines only

#### IF YOU CONFIRM

The following, or the customer reports the following:

Intermittently there is low power when accelerating,

And/or

 The stop lamps (brake lights) stay ON after releasing the brake pedal, with the ignition ON or OFF.

#### **ACTION**

- Delete the stop lamp relay.
- 2. Replace the stop lamp switch with the one listed in **PARTS INFORMATION**.
- 3. Install brake light switch bypass harness.

**IMPORTANT**: The purpose of "ACTION" (above) is to give you a quick idea of the work you will be performing. You MUST closely follow the entire Service Procedure as it contains information that is essential to successfully completing the repair.

Nissan Bulletins are intended for use by qualified technicians, not 'do-it-yourselfers'. Qualified technicians are properly trained individuals who have the equipment, tools, safety instruction, and know-how to do a job properly and safely. NOTE: If you believe that a described condition may apply to a particular vehicle, DO NOT assume that it does. See your Nissan dealer to determine if this applies to your vehicle.

#### **SERVICE PROCEDURE**

## **Stop Lamp Relay Deletion**

- 1. Remove the stop lamp fuse (#10) from the "junction box" fuse block in the Instrument panel.
- 2. Remove "fuse and relay box" (fuse box) cover and locate stop lamp relay (Figure 1).
  - Fuse box located on bulkhead (engine wall) above engine.




Figure 1

3. Remove the stop lamp relay (Figure 2).

**NOTE:** This relay will not be reinstalled.




Figure 2

#### **Brake Light Switch Bypass Harness Installation**

- 1. Remove instrument lower panel LH
  - Refer to the Electronic Service Manual (ESM), section IP – Instrument Panel for removal information.





Figure 3

- 2. Disconnect harness connector E28, shown in Figure 4, from the back of Fuse Block (J/B).
  - If needed refer to the Electronic ESM, section PG Power Supply, Ground & Circuit Elements for further information on harness connector E28 and Fuse Block (J/B).

**NOTE:** Fuse Block (J/B) is shown detached from support bracket. Harness connector E28 can be disconnected with Fuse Block (J/B) left in place.



3. Connect jumper harness (part #: 24167-9PB1E) between Fuse Block (J/B) and harness connector E28 (Figure 5).




Figure 5

4. Tuck "harness connector E28/jumper harness" behind Fuse Block (J/B).




Figure 6

5. Tape harness connector E28/jumper harness to the main harness.




Figure 7

6. Route the jumper harness behind the support bracket as shown in Figure 8.




Figure 8

- 7. Clip the jumper harness to the support bracket (Figure 9).
- 8. Zip tie the jumper harness to the side of the support bracket (Figure 9).




Figure 9

9. Locate the stop lamp switch connector and disconnect it from stop lamp switch.





Figure 10



protective cap that covers the end of the single wire.

in vehicle harness (Figure 11).

9PB2E).

Figure 11




Figure 12

- 12. Replace the stop lamp switch with the part listed in **PARTS INFORMATION**.
  - Refer to the ESM, section BR Brake System / Brake Pedal for replacement information and adjustment.







Figure 13 Figure 14

- 13. Connect the sub-harness to the stop lamp switch (Figure 15).
- 14. Unclip the stop lamp harness from the support bracket (Figure 16).



- Tape the harness so that the subharness is facing downward.
- Apply the tape above the harness clip.
- 16. Re-attach the stop lamp harness to the support bracket.
- 17. Reassembly the instrument lower panel LH in the reverse order of disassembly.





Figure 15



## **PARTS INFORMATION**

DESCRIPTION	PART NUMBER	QUANTITY
Stop Lamp Switch	25320-AX10A	1
Jumper Harness	24167-9PB1E	1
Sub-Harness	24167-9PB2E	1





Figure 17 Figure 18

## **CLAIMS INFORMATION**

Submit a Primary Part (PP) type line claim using the following claims coding:

OPERATION	PFP	OP CODE	SYM	DIAG	FRT
Delete Brake Light Relay	25230-79917	PX83AA	ZE	32	0.5 hrs.