

2017

Q7/Q7 TDI

Audi Technician Report

Stock No. De	ealer Number		R.O. No.		
VIN Road test mileage out			Road test mileage in		
All items must be completed prior to custo	omer delivery by an A	Audi technician			
 Audi recommends using an Audi approved 	battery charger to p	revent excessive batte	ery discharge during inspection		
 All PDI function tests must be run in Guid- these will not be uploaded to the Paperles function tests. 	_	-	=		
 It is advised to start ODIS with the engine during the SVM check vehicle configuratio 	-	ll 5F Test Plans in GFF	and also to ensure SVM sees all control units		
For items marked with *, please refer to the	ne PDI Technician Ref	ference Document pos	ted on ServiceNet for additional information		
Vehicle Preparation		Trunk Inspection (d	continued)		
Check Elsa for open campaigns and updates		☐ Verify inflatable repair kit & compressor are present			
Deactivate vehicle transport mode* This step must be performed with the engine off and ignition on		Set spare tire pressure* Interior			
Set adaption channel to enable CD Ripping (if equipped with NAV)* Set service reminder* Perform any open campaigns*		☐ Verify operation of all seat belts and latches			
		Check operation of windows and locks*			
		Check rear view mirror operation*			
		☐ Inspect mirrors for proper operation*			
Under the Hood Inspection		☐ Verify operation of all interior lights			
Check battery clamps for proper torque* Perform a battery test* Check engine oil level* Check all fluid levels and top off if necessary		 □ Verify SOS button is green and Roadside assistance button LED will remain off (if equipped) □ Check heated steering wheel operation (if equipped) □ Verify operation front heated seats* 			
				☐ Verify operation front ventilated seats (if equipped)	
				Exterior	
		☐ Check all key buttons and features*		☐ Verify operation of rear heated seats (if equipped)	
Check all doors for proper power closing (if equipped)*		☐ Verify operation of manual folding 2nd row and power folding 3rd row seats*			
Lighting and Windshield		☐ Verify proper oper	ration of climate control*		
Test exterior lighting functions		☐ Inspect operation of all power outlets			
Test front washers (and headlight washers if equipped)*		☐ Check panoramic sunroof & sunshade operation*			
		☐ Verify the glove compartment opens and closes properly			
Trunk Inspection Verify power tailgate is operational and set default opening height*		☐ Verify operation of front Passenger Occupant Detection System			
		☐ Verify operation o	f rear side manual sunshades (if equipped)		
Install wheel bolt cover removal tool from PDI kit into trunk tool kit*		Settings			
Verify tool kit is installed securely in luggage compartment		☐ Verify operation of MMI touch pad (if equipped)			

Effective 7-15-2016-US Version 1.4

☐ Verify tool kit is installed securely in luggage compartment



2017

Q7/Q7 TDI

Audi Technician Report

Settings (continued)	Driving Performance		
Set Time to "Automatic setting" and "Automatic time zone"	Check horn operation		
☐ Verify and set language and Measurement Units*	☐ Verify hold and release of electronic parking brake		
☐ Verify Speech dialog system is operating*	☐ Verify engine Start-Stop System functionality*		
Set "Entertain. Fad." in Parking aid to Medium*	☐ Verify engine performance and acceleration*		
☐ Load Onboard Video Tutorials*	Verify transmission operation, including shift paddles		
Set dealership location in navigation (if equipped)*	☐ Test drive vehicle applying brakes several times*		
☐ Turn off Manual Speed Warning*	Check adaptive air suspension in all positions (if equipped)		
Media / Radio / SAT	Check steering/tire alignment		
☐ Verify operation of CD/DVD player	Verify operation of all-wheel steering with vehicle speed- dependent control (if equipped)*		
☐ Insert SD card and test function of all slots	Check for squeaks, rattles and wind noise		
Program the presets to local stations	Verify quality of radio reception in AM/FM/SiriusXM bands		
☐ Verify HD Radio is turned "off"*			
	Driver Assistance		
Audi connect (USA ONLY) (if equipped) Verify Audi connect Information Packet is present (if	Verify cruise control and ACC with Traffic jam assist (congestion assist) (if equipped)		
equipped)*	☐ Verify Audi active lane assist functionality (if equipped)		
□ Verify system connects to mobile network (if equipped). Review TSB 2042942 for additional information*	Verify Audi side assist functionality Pre sense rear (if equipped)*		
☐ Turn on the wireless network (if equipped)*	Verify operation of night vision camera (if equipped)		
Check Wi-Fi hotspot visibility. No data available at PDI (if	☐ Verify operation of parking system plus*		
equipped)*	☐ Verify operation of Traffic sign recognition (if equipped)		
☐ Enable Google Earth (if equipped)*	Verify all vehicle Head-up Display functionality (if equipped)*		
On-Hoist Inspection	Verify operation of High-beam assist (if equipped)		
Check steering, boots, brake system, hoses, tires and wheels for damage	Activate NAV and follow directions back to dealership (if		
$\hfill \square$ Check underside of vehicle for fluid leaks and loose components	equipped)		
☐ Inspect wheel bolts for proper torque*	Post-Road Test Inspection		
☐ Install wheel locks (if equipped)	☐ Interrogate fault memory and print Diagnostic Log		
☐ Install wheel bolt covers and center caps as supplied* ☐ Set and store tire pressures for either sold vehicle OR stock	☐ Ensure the yellow tire pressure tag is installed on the steering wheel		
inventory vehicle*	Apply Inventory Maintenance Sticker		
	Install showroom charger to ensure battery remains charged at all times		
//// Technician			
I certify that all operations have been completed and this vehi Quality Standards, and has met the standards for Perfect Deli	icle has been prepared in accordance with Audi Procedures and very.		
Technician Signature La:	st 8 of VIN Completion Date		