

#### 2018

### A5/S5

## Audi Pre-Delivery Inspection

Stock No. De	Dealer Number  Road test mileage out		R.O. No.	
VIN Ro			Road test mileage in	
Reminders				
► All items must be completed prior to custo	mer delivery by an <i>F</i>	Audi technician		
► Audi recommends using an Audi approved	battery charger to p	revent excessive batte	ry discharge during inspection	
ALL PDI function tests must be run in Guid as these will not be uploaded to the Paperl function tests	_	_	Guided Functions for any PDI related test tab of ODIS Diagnosis for using GFF for PDI	
► It is advised to start ODIS with the engine during the SVM check vehicle configuration	_	ll 5F Test Plans in GFF	and also to ensure SVM sees all control units	
► For items marked with *, please refer to the	e PDI Technician Ref	erence Document post	ted on ServiceNet for additional information	
► For items marked with **, follow instruction	ns for stock invento	ory vehicle		
Vehicle Preparation		Interior		
☐ Check Elsa for open campaigns and update	S	☐ Verify operation	of all seat belts and latches	
☐ Deactivate vehicle transport mode*		☐ Check operation of window, lock, and seat controls*		
This step must be performed with the e	engine off, and igni-	☐ Inspect mirrors f	for proper operation*	
tion on	(if aguinged with	Check rear view r	nirror operation*	
Set adaption channel to enable CD Ripping (if equipped wit NAV)*		☐ Verify operation of all interior lights		
Set service reminder*		☐ Verify SOS button is green and Roadside assistance button LED will remain off (if equipped)		
Perform any open campaigns*				
_ , , , ,		☐ Verify operation	heated/ventilated seats (if equipped)	
Exterior		☐ Verify proper ope	eration of climate control*	
Check all key buttons and features*		☐ Inspect operatio	n of all power outlets*	
Inspect exterior for damage, dings, dents a scratches	nts and surface	☐ Verify the glove of	compartment opens and closes properly	
Scratches		Check panoramic	sunroof and sunshade operation*	
Lighting and Windshield		_ , ,	of front Passenger Occupant Detection	
☐ Test exterior lighting functions		System		
☐ Test front washers (and headlight washers	if equipped)*	Settings		
- I		☐ Verify operation	of MMI® touch pad (if equipped)	
Trunk Inspection  ☐ Verify trunk is operational  ☐ Verify operation of emergency release handle  ☐ Install wheel bolt cover removal tool from PDI kit into trunk tool kit*		☐ Set Time source setting to "GPS" and set Auto daylight savings time to "on."*		
		Set Time to "Automatic setting" and "Automatic time zone"		
			nguage and measurement units*	

Effective 6-20-2017-US Version 1.1

☐ Set spare tire pressure\*

☐ Check battery clamps for proper torque\*

☐ Verify tool kit is installed securely in luggage compartment

☐ Verify Speech Dialog System is operating\*

☐ Set "Music volume while parking" to 6 lines\*

☐ Set "Entertain. Fad." in Parking aid to an audible level\*

☐ Set dealership location in navigation (if equipped)\*



### 2018

Version 1.1

### A5/S5

# Audi Pre-Delivery Inspection

Settings (continued)	Driving Performance (continued)		
☐ Turn off Manual Speed Warning (if equipped)*	Verify transmission operation, including shift paddles (if equipped)		
Media / Radio / SAT	☐ Test drive vehicle applying brakes several times*		
☐ Verify operation of AMI or aux. input (if equipped)	Check steering/tire alignment		
☐ Verify operation of CD/DVD player (if equipped)	Check for squeaks, rattles and wind noise		
☐ Insert SD card and test function of all slots	Calibrate rear view mirror*		
☐ Verify HD Radio is turned "off"*	☐ Verify quality of radio reception in AM/FM/SiriusXM® bands		
Audi connect® (USA ONLY) (if equipped)	Driver Assistance		
☐ Verify Audi connect® Information Packet is present (if equipped)*	Verify cruise control/ACC with Stop & Go functionality (if equipped)		
$\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ $	☐ Verify Audi side assist functionality (if equipped)		
sold in DMS, data is only available after customer starts 6-month trial in <a href="www.myaudiconnect.com">www.myaudiconnect.com</a> )	☐ Verify Audi active lane assist functionality (if equipped)		
Turn on the wireless network (if equipped)*	Verify operation of parking system (if equipped)*		
Check Wi-Fi® hotspot functionality*	Verify all vehicle Head-up display functionality (if equipped)*		
☐ Enable Google Earth™ (if equipped)*	Activate NAV and follow directions back to dealership (if equipped)		
On-Hoist Inspection			
Remove transport suspension blocks (follow ELSA instruction)	Convertible Functionality (if equipped)		
Check steering, boots, brake system, hoses, tires and wheels for damage	☐ Test operation of power folding top* ☐ Verify convertible top manual closing tools are present		
Check underside of vehicle for fluid leaks and loose components	·		
☐ Install wheel locks (if equipped)	Post-Road Test Inspection  Interrogate fault memory and upload Diagnostic Log to GFF Paperless Server		
☐ Install wheel bolt covers and center caps as supplied*			
☐ Inspect wheel bolts for proper torque*	Perform a battery test*		
Set and store tire pressures for either sold vehicle <b>OR</b> stock inventory vehicle*	Check Service Interval and verify correct interval is displayed*		
Duiving Boufermans	Check engine oil level*		
Driving Performance  Check horn operation	☐ Check all fluid levels and top off if necessary		
☐ Verify hold and release of electronic parking brake	Ensure the yellow tire pressure tag is installed on the steering wheel		
☐ Verify engine Start-Stop System functionality*	Apply Inventory Maintenance Sticker**		
☐ Verify engine performance and acceleration*	Install showroom charger to ensure battery remains charged at all times**		
	://////		
Technician  I certify that all operations have been completed and this verified Quality Standards, and has met the standards for Perfect December 1.	chicle has been prepared in accordance with Audi Procedures and celivery.		
Technician Signature	Last 8 of VIN Completion Date		
<i>\\\\\\\\</i>	//////		
//////// Effective 6-20-2017-US	PRE-DELIVERY INSPECTION (PDI)   2		