

2018

A4/S4/A4 allroad

Audi Pre-Delivery Inspection

| Stock No. | Dealer Number | R.O. No. | | | | | |
|--|---|--|--|--|--|--|--|
| VIN | Road test mileage out | Road test mileage in | | | | | |
| Reminders | | | | | | | |
| | o customer delivery by an A | Audi technician | | | | | |
| | All items must be completed prior to customer delivery by an Audi technician Audi recommends using an Audi approved battery charger to prevent excessive battery discharge during inspection | | | | | | |
| ► ALL PDI function tests must be run | in Guided Fault Finding (G | FF) only. Do NOT use Guided Functions for any PDI related test the Special functions tab of ODIS Diagnosis for using GFF for PDI | | | | | |
| ► It is advised to start ODIS with the oduring the SVM check vehicle config | | all 5F Test Plans in GFF and also to ensure SVM sees all control units | | | | | |
| ► For items marked with *, please refe | er to the PDI Technician Ref | ference Document posted on ServiceNet for additional information | | | | | |
| ► For items marked with **, follow ins | structions for stock invento | ory vehicle | | | | | |
| Vehicle Preparation | | Trunk Inspection (continued) | | | | | |
| Check Elsa for open campaigns and updates | | Set spare tire pressure* | | | | | |
| ☐ Deactivate vehicle transport mode* This step must be performed with the engine off , and ignition on | | ☐ Check battery clamps for proper torque* | | | | | |
| | | Interior | | | | | |
| ☐ Set adaption channel to enable CD Ripping (if equipped with NAV)* ☐ Set service reminder* | | \square Verify operation of all seat belts and latches | | | | | |
| | | ☐ Check operation of window, lock, and seat controls* | | | | | |
| Perform any open campaigns* | | ☐ Inspect mirrors for proper operation* | | | | | |
| | | ☐ Check rear view mirror operation* | | | | | |
| Exterior | | ☐ Verify operation of all interior lights | | | | | |
| ☐ Inspect exterior for damage, dings, dents and surface scratches | | ☐ Verify SOS button is green and Roadside assistance button LED will remain off (if equipped) | | | | | |
| ☐ Check all key buttons and features* | | ☐ Verify operation of heated/ventilated seats (if equipped) | | | | | |
| | | ☐ Verify proper operation of climate control* | | | | | |
| Lighting and Windshield | | ☐ Inspect operation of all power outlets* | | | | | |
| ☐ Test exterior lighting functions☐ Test front washers (and headlight washers if equipped)* | | ☐ Check panoramic sunroof and sunshade operation* | | | | | |
| | | $\hfill \Box$ Verify the glove compartment opens and closes properly | | | | | |
| Trunk Inspection | | ☐ Verify operation of front Passenger Occupant Detection | | | | | |
| Verify trunk is operational | | System | | | | | |
| ☐ Verify operation of emergency relea | se handle | Settings | | | | | |
| ☐ Install wheel bolt cover removal tool from PDI kit into trunk | | Set Time source setting to "GPS" and set Auto daylight sav- | | | | | |

ings time to "on"*

☐ Verify operation of MMI touch pad (if equipped)

☐ Set Time to "Automatic setting" and "Automatic time zone"

Effective 3-15-2017-US Version 1.2

 $\hfill \square$ Verify tool kit is installed securely in luggage compartment

 $\hfill \Box$ Verify inflatable spare tire and compressor are present



2018

A4/S4/A4 allroad

Audi Pre-Delivery Inspection

| Settings (continued) | Driving Performance (continued) | | |
|---|---|--|--|
| ☐ Verify and set language and Measurement Units* | ☐ Verify engine Start-Stop System functionality* | | |
| ☐ Verify Speech dialog system is operating* | ☐ Verify engine performance and acceleration* | | |
| ☐ Set "Entertain. Fad." in Parking aid to an audible level* | ☐ Verify transmission operation, including shift paddles (if equipped) | | |
| ☐ Set "Music volume while parking" to 6 lines* | | | |
| ☐ Set dealership location in navigation (if equipped)* | ☐ Test drive vehicle applying brakes several times* | | |
| ☐ Turn off Manual Speed Warning (if equipped)* | Check steering/tire alignment | | |
| | ☐ Check for squeaks, rattles and wind noise | | |
| Media / Radio / SAT | Calibrate rear view mirror* | | |
| ☐ Verify operation of AMI or aux. input (if equipped) | ☐ Verify quality of radio reception in AM/FM/SiriusXM bands | | |
| ☐ Verify operation of CD/DVD player (if equipped) | Duiyon Assistance | | |
| ☐ Insert SD card and test function of all slots | Driver Assistance | | |
| Program the presets to local stations | ☐ Verify cruise control/ACC functionality (if equipped) | | |
| ☐ Verify HD Radio is turned "off"* | ☐ Verify Audi side assist functionality (if equipped) | | |
| Audi connect (USA ONLY) (if equipped) | ☐ Verify operation of parking system (if equipped)* | | |
| • • • | ☐ Verify all vehicle Head-up display functionality (if equipped)* | | |
| □ Verify Audi connect Information Packet is present (if equipped)* | Activate NAV and follow directions back to dealership (if equipped) | | |
| Check LTE connection is possible (if vehicle is marked retail sold in DMS, data is only available after customer starts | Post-Road Test Inspection | | |
| 6-month trial in <u>www.myaudiconnect.com</u>) | ☐ Interrogate fault memory and upload Diagnostic Log to GFF | | |
| ☐ Turn on the wireless network (if equipped)* | Paperless Server | | |
| ☐ Check Wi-Fi hotspot visibility (if equipped)* | ☐ Check Service Interval and verify correct interval is displayed* | | |
| ☐ Enable Google Earth (if equipped)* | | | |
| | Check engine oil level* | | |
| On-Hoist Inspection | Check all fluid levels and top off if necessary | | |
| Remove transport suspension blocks (follow ELSA instruc- | Perform a battery test* | | |
| tion) Check steering, boots, brake system, hoses, tires and wheels | ☐ Ensure the yellow tire pressure tag is installed on the steering wheel | | |
| for damage | Apply Inventory Maintenance Sticker** | | |
| ☐ Check underside of vehicle for fluid leaks and loose components | Install showroom charger to ensure battery remains charged at all times** | | |
| ☐ Inspect wheel bolts for proper torque* | | | |
| ☐ Install wheel locks (if equipped) | | | |
| ☐ Install wheel bolt covers and center caps as supplied* | | | |
| Set and store tire pressures for either sold vehicle OR stock inventory vehicle* | | | |
| Driving Performance | | | |
| Check horn operation | | | |
| ☐ Verify hold and release of electronic parking brake | | | |

Effective 3-15-2017-US Version 1.2



2018

A4/S4/A4 allroad

Audi Pre-Delivery Inspection

| <i>\\\\</i> , | Technician | | | | | | |
|---------------|--|---------------|-----------------|---------------|--|--|--|
| '/// | I certify that all operations have been completed and this vehicle has been prepared in accordance with Audi Procedures and Quality Standards, and has met the standards for Perfect Delivery. | | | | | | |
| | Technician Signature | Last 8 of VIN | Completion Date | - '/// | | | |
| /////// | | | | <i>\\\\\\</i> | | | |