





Subject Front Door Lower Exterior Molding Gap		Market USA
Service Category Vehicle Exterior	Section Door/Hatch	
Applicability 2017-Present Highlander / HV2018 Highlander / HV		

APPLICABLE VEHICLES

2017-2018	Highlander	2017-2018	Highlander HV
-----------	------------	-----------	---------------

CONDITION

Some vehicles may experience a condition in which the LH or RH front door outside molding exhibits a gap, looseness or separation from the outer door panel.



RECOMMENDATIONS

Please document the following during diagnosis and repair of the vehicle and submit a DPR:

- Overall photograph of affected door.
- Location of gap, looseness or separation between door molding and outer door panel.
 - Photograph door with masking tape to mark location of gap and measure distance from front of door to center of gap location.
- Inspect installation condition of molding retaining clips during disassembly.
 - Photograph location of clip(s) damaged or improperly installed into molding and/or outer door panel. If photo is unavailable, include description of clip installation condition.
 - Include measurement of distance from front of door to affected clip(s).
- Inspect double sided tape condition during disassembly.
 - Photograph tape condition in affected area for signs of dust or separation of tape.

LINK REFERENCES

1. [EXTERIOR PANELS / TRIM: FRONT DOOR OUTSIDE MOULDING: REMOVAL; 2014 - 2018 MY Highlander \[12/2013 - ???????\]](#)