

2019

A7

## Audi Pre-Delivery Inspection

Stock No.

Dealer Number

R.O. No.

VIN

Road test mileage out

Road test mileage in

### Reminders

- ▶ All items must be completed prior to customer delivery by an Audi technician
- ▶ Audi recommends using an Audi approved battery charger to prevent excessive battery discharge during inspection
- ▶ ALL PDI function tests must be run in Guided Fault Finding (GFF) using PDI Total Function Test Plan only. Do NOT use Guided Functions for any PDI related test as these will not be uploaded to the Paperless Server. Refer to the Special functions tab of ODIS Diagnosis for using GFF for PDI function tests
- ▶ It is advised to start ODIS with the engine running to enable all 5F Test Plans in GFF
- ▶ For items marked with \*, please refer to the PDI Technician Reference Document posted on ServiceNet for additional information
- ▶ For items marked with \*\*, follow instructions for stock inventory vehicle

### Vehicle Preparation

- Check Elsa for open campaigns and updates
- Deactivate vehicle transport mode\*  
**This step must be performed with the engine off, and ignition on\***  
**Note: The VAS 6154 diagnostic head is required along with ODIS Audi Brand version 2.15.5 or higher\***
- Deactivate air suspension loading mode (if equipped)\*
- Set service reminder\*
- Perform any open campaigns\*
- Set the service intervals to 10k instead of 5k during PDI or existing 2017 vehicles that are set incorrectly
  1. Click on the "Special functions" tab
  2. Scroll down to 'Maintenance'
  3. Select the 17 - inspection with oil change - 10,000 miles, USA function test
  4. Perform the function test, but make sure you select "USA" as the country variant and when the question "Which service display should be reset?" comes up, select #2 (Oil service display and inspection service display).
  5. Then the MMI® indicator should now properly display the following values
    - Next oil service in 10,000 miles / 365 days
    - Next inspection service at 20,000 miles / 730 days

### Exterior

- Check all key buttons and features\*
- Check all doors for proper power closing (if equipped)\*

### Exterior (continued)

- Inspect exterior for damage, dings, dents and surface scratches

### Lighting and Windshield

- Test exterior lighting functions
- Test front washers (and headlight washers if equipped)\*
- Install wiper blades

### Trunk Inspection

- Verify trunk is operational
- Install wheel bolt cover removal tool from PDI kit into trunk tool kit\*
- Verify tool kit is installed securely in luggage compartment
- Set spare tire pressure (if equipped)\*
- Check battery clamps for proper torque\*

### Interior

- Verify operation of all seat belts and latches
- Check operation of window, lock, and seat controls\*
- Inspect mirrors for proper operation\*
- Check rear view mirror operation\*
- Verify operation of all interior lights
- Check heated steering wheel operation (if equipped)
- Verify operation heated/ventilated and massaging seats (if equipped)\*
- Verify operation of manual folding 2nd row



2019

A7

## Audi Pre-Delivery Inspection

### Interior (continued)

- Verify proper operation of climate control\*
- Inspect operation of all power outlets\*
- Check sunroof and sunshade operation\*
- Verify operation of front Passenger Occupant Detection System
- Verify operation of rear side manual sunshades (if equipped)
- Verify operation of power rear sunshade (if equipped)

### Settings

- Verify operation of MMI® touch screens, upper and lower
- Set Time source setting to “GPS” and set Auto daylight savings time to “on”\*
- Verify and set language and measurement units\*
- Verify Speech Dialog System is operating\*
- Set “Music volume while parking” to medium\*
- Set dealership location in navigation\*
- Turn off Manual Speed Warning (if equipped)\*

### Media / Radio / SAT

- Verify operation of all USB ports
- Verify operation of aux. input
- Verify operation of CD/DVD player (if equipped)
- Insert SD card and test function of slot
- Program the presets to local stations
- Verify HD Radio is turned “off”\*
- Verify Audi phone box sticker and registration information is present (if equipped)

### Audi connect® (USA ONLY)

- Turn on the Wi-Fi® hotspot (if equipped)\*
- Check Wi-Fi® hotspot visibility. No data available at PDI due to dealer demo mode (if equipped)\*
- Enable satellite map for navigation (if equipped)\*

### On-Hoist Inspection

- Remove transport suspension blocks (follow ELSA instruction)
- Check steering, boots, brake system, hoses, tires and wheels for damage
- Check underside of vehicle for fluid leaks and loose components

### On-Hoist Inspection (continued)

- Install wheel locks (if equipped)
- Install wheel bolt covers and center caps as supplied\*
- Inspect wheel bolts for proper torque\*
- Set and store tire pressures for either sold vehicle **OR** stock inventory vehicle\*

### Driving Performance

- Check horn operation
- Verify hold and release of electronic parking brake
- Verify engine Start-Stop System functionality\*
- Verify engine performance and acceleration\*
- Verify transmission operation, including shift paddles
- Test drive vehicle applying brakes several times\*
- Check adaptive air suspension in all positions (if equipped)
- Verify rear spoiler functionality (if equipped)
- Check steering/tire alignment
- Check for squeaks, rattles and wind noise
- Calibrate rear view mirror\*
- Verify quality of radio reception in AM/FM/SiriusXM® bands

### Driver Assistance

- Verify all cruise control functions
- Verify cruise control/ACC with Stop & Go functionality (if equipped), which includes the following:
  - Adaptive Cruise Assist
  - Turn Assist
  - Intersection Assistant
  - Traffic Jam Assist
  - Predictive Efficiency Assist
  - Active lane assist with emergency assistant
  - Traffic sign recognition
- Verify Audi side assist functionality Pre sense® rear (if equipped)
- Verify operation of night vision camera (if equipped)
- Verify operation of parking system\*
- Verify all vehicle Head-up display functionality (if equipped)\*
- Verify operation of High-beam assistant (if equipped)
- Activate NAV and follow directions back to dealership



2019

A7

## Audi Pre-Delivery Inspection

### Post-Road Test Inspection

- Interrogate fault memory and upload diagnostic log to GFF Paperless Server
- Perform a battery test\*
- Check service interval and verify correct interval is displayed
- Check engine oil level\*
- Check all fluid levels and top off if necessary
- Ensure the yellow tire pressure tag is installed on the steering wheel
- Apply Inventory Maintenance Sticker\*\*
- Install showroom charger to ensure battery remains charged at all times\*\*

### Technician

I certify that all operations have been completed and this vehicle has been prepared in accordance with Audi Procedures and Quality Standards, and has met the standards for Perfect Delivery.

\_\_\_\_\_  
Technician Signature

\_\_\_\_\_  
Last 8 of VIN

\_\_\_\_\_  
Completion Date