

2019

A8 L Audi Pre-Delivery Inspection

Stock N	lo.
---------	-----

Dealer Number

R.O. No.

VIN

Road test mileage out

Road test mileage in

Reminders

- All items must be completed prior to customer delivery by an Audi technician
- Audi recommends using an Audi approved battery charger to prevent excessive battery discharge during inspection
- ALL PDI function tests must be run in Guided Fault Finding (GFF) using PDI Total Function Test Plan only. Do NOT use Guided Functions for any PDI related test as these will not be uploaded to the Paperless Server. Refer to the Special functions tab of ODIS Diagnosis for using GFF for PDI function tests
- It is advised to start ODIS with the engine running to enable all 5F Test Plans in GFF
- For items marked with *, please refer to the PDI Technician Reference Document posted on ServiceNet for additional information
- ▶ For items marked with **, follow instructions for stock inventory vehicle

Vehicle Preparation

Check Elsa for open campaigns and updates

Deactivate vehicle transport mode*
This step must be performed with the engine off, and ignition on*
Note: The VAS 6154 diagnostic head is required along with

ODIS Audi Brand version 2.15.5 or higher*

- Deactivate air suspension loading mode (if equipped)*
- Set service reminder*
- Perform any open campaigns*

Set the service intervals to 10k instead of 5k during PDI or existing 2017 vehicles that are set incorrectly

- 1. Click on the "Special functions" tab
- 2. Scroll down to 'Maintenance
- 3. Select the 17 inspection with oil change 10,000 miles, USA function test
- 4. Perform the function test, but make sure you select "USA" as the country variant and when the question "Which service display should be reset?" comes up, select #2 (Oil service display and inspection service display).
- 5. Then the MMI® indicator should now properly display the following values
 - Next oil service in 10,000 miles / 365 days
 - Next inspection service at 20,000 miles / 730 days

Exterior

Check all key buttons and features*

Check all doors for proper power closing*

Exterior (continued)

Inspect exterior for damage, dings, dents and surface scratches

Lighting and Windshield

- Test exterior lighting functions
- Test front washers (and headlight washers)*
- Install wiper blades

Trunk Inspection

- Verify trunk is operational
- □ Verify operation of emergency release handle
- Install wheel bolt cover removal tool from PDI kit into trunk tool kit*
- Verify tool kit is installed securely in luggage compartment
- Set spare tire pressure*
- Check battery clamps for proper torque*

Interior

- □ Verify operation of all seat belts and latches*
- Check operation of window, lock, and seat controls*
- □ Inspect mirrors for proper operation*
- Check rear view mirror operation*
- ☐ Verify operation of all interior lights
- Check heated steering wheel operation (if equipped)
- Verify operation of heated/ventilated and massaging seats (if equipped)*

PRE-DELIVERY INSPECTION (PDI) | 1



2019

A8 L

Audi Pre-Delivery Inspection

Interior (continued)

- □ Verify operation of manual folding 2nd row
- □ Verify proper operation of climate control*
- ☐ Inspect operation of all power outlets*
- Check panoramic sunroof and sunshade operation*
- $\hfill \Box$ Verify operation of power rear and rear side sunshade operation
- □ Verify operation of front Passenger Occupant Detection System
- Verify operation of heated surfaces (front/rear) (if equipped)

Settings

- □ Verify operation of MMI® touch screens, upper and lower
- Set Time source setting to "GPS" and set Auto daylight savings time to "on"*
- □ Verify and set language and measurement units*
- □ Verify Speech Dialog System is operating*
- Set "Music volume while parking" to medium*
- Set dealership location in navigation*
- □ Turn off Manual Speed Warning (if equipped)*

Media / Radio / SAT

- □ Verify operation of aux. input (if equipped)
- □ Verify operation of CD/DVD player (if equipped)
- ☐ Insert SD card and test function of all slots
- $\hfill\square$ Program the presets to local stations
- □ Verify HD Radio is turned "off"*
- □ Verify operation of Rear Seat Entertainment (if equipped)
- Verify Audi phone box sticker and registration information is present (if equipped)

Audi connect® (USA ONLY)

- Turn on the Wi-Fi[®] hotspot (if equipped)*
- ☐ Check Wi-Fi[®] hotspot visibility. No data available at PDI due to dealer demo mode (if equipped)*
- □ Enable satellite map for navigation (if equipped)*

On-Hoist Inspection

- Remove transport suspension blocks (follow ELSA instructions)
- Check underside of vehicle for fluid leaks and loose components
- Check steering, boots, brake system, hoses, tires and wheels for damage

On-Hoist Inspection (continued)

- ☐ Install wheel locks (if equipped)
- □ Install wheel bolt covers and center caps as supplied*
- □ Inspect wheel bolts for proper torque*
- Set and store tire pressures for either sold vehicle OR stock inventory vehicle*

Driving Performance

- Check horn operation
- □ Verify hold and release of electronic parking brake
- □ Verify engine Start-Stop System functionality*
- □ Verify engine performance and acceleration*
- Verify transmission operation, including shift paddles (if equipped)
- Test drive vehicle applying brakes several times*
- Check adaptive air suspension in all positions (if equipped)
- Check steering/tire alignment
- Check for squeaks, rattles and wind noise
- Calibrate rear view mirror*
- □ Verify quality of radio reception in AM/FM/SiriusXM[®] bands

Driver Assistance

- □ Verify all cruise control functions
- □ Verify cruise control/ACC with Stop & Go functionality (if equipped), which includes the following:
 - 🗌 Adaptive Cruise Assist
 - 🗌 Turn Assist
 - Intersection Assistant
 - 🗌 Traffic Jam Assist
 - Predictive Efficiency Assist
 - Active lane assist with emergency assistant
 - Traffic sign recognition
- Verify Audi side assist functionality Pre sense[®] rear (if equipped)
- □ Verify operation of night vision camera (if equipped)
- □ Verify operation of parking system*
- □ Verify all vehicle Head-up display functionality (if equipped)*
- □ Verify operation of High-beam assist
- $\hfill \square$ Activate NAV and follow directions back to dealership

Effective 9-17-2018-US Version 1.0



2019

A8 L Audi Pre-Delivery Inspection

Post-Road Test Inspection

☐ Interrogate fault memory and upload diagnostic log GFF Paperless Server	to		
Perform a battery test*			
Check service interval and verify correct interval is di played	S-		
Check engine oil level*			
Check all fluid levels and top off if necessary			
Ensure the yellow tire pressure tag is installed on the steering wheel	e		
Apply Inventory Maintenance Sticker**			
Install showroom charger to ensure battery remains charged at all times**			
//// Technician			
I certify that all operations have been completed an Quality Standards, and has met the standards for Pe		d in accordance with Audi Procedures and	
Technician Signature	Last 8 of VIN	Completion Date	- '///