




Technical Information Bulletin

34-073



Section

Wiring and Lighting - 34

Subject

T680/T880/W990 VECU May Wake Up Every 2 Minutes When Low Voltage Disconnect (LVD) Is Enabled

Release Date

12/5/2018

Condition

The vehicle may have the following symptoms:

- The VECU may wake up every 2 minutes after LVD is enabled.
 - The reverse lights turn on every 2 minutes on vehicles equipped with a manual transmission when the vehicle is parked in reverse and in LVD mode.
 - The dash Driver Information Display (in the Speedo/Tach cluster) may illuminate every 2 minutes.
-

Chassis Affected

T680, T880, and W990 vehicles built from 06/04/2018 through 12/02/2018 equipped with a VECU.

Action

Fix-As-Fail

If a customer comes into your dealership and demonstrates the condition above, update the CECU software using the Procedure below.

Warranty

Through Standard Warranty (includes Extended Warranty) Kenworth will pay for labor:

- 0.3 hours labor to update the CECU software. Use Quick Claim Code 34073.
- File an additional claim for extraordinary circumstances. A quick claim for standard labor must be filed first.

Take-Off Parts Disposition: N/A

CLAIM CODING			
Failure Location:	003-001-082	Work Accomplished:	58
Failure Type:	363	Responsibility Code:	01
SRT Code:	045-066 0.3 hrs. Reflash CECU, ICU or Update ESA Parameters in chassis with 2010/2013/2017- emissions engines	Claim Type:	N

Parts

No parts required. Software update only.

Procedure

Refer to bulletin [03-064](#) for ESA best practices.

The repair for this issue is to update CECU3-500 software P30-1041-101 to P30-1041-104.

1. Update ESA.
2. Connect ESA to the vehicle.
3. Update the CECU3-500 software.

Authored by: OF

Access to PACCAR's Enterprise Portal is provided as a benefit of doing business with PACCAR. All applications and content accessed through this system are confidential and proprietary and the property of PACCAR Inc and its suppliers, and must be kept strictly confidential pursuant to the contract licensing such access. Disclosure, publication, release or distribution of any material found on PACCAR systems to any person other than employees with a need to know such information is strictly

prohibited. All activity on this system is monitored. If PACCAR suspects or discovers any unauthorized activity, access may be immediately terminated without prior notification. Violators may be subject to legal action.

© Copyright 2019 PACCAR Inc. All rights reserved. We welcome your [feedback](#) on this page. For technical questions or concerns about this page, please contact the [DealerNet Webmaster](#).