



**Countries:** AUSTRALIA, BAHAMAS, BOLIVIA, BRAZIL, BELIZE, CANADA, CHILE, TAIWAN, COLOMBIA, COSTA RICA, DOMINICAN REPUBLIC, ECUADOR, EL SALVADOR, TRINIDAD AND TOBAGO, UNITED STATES, URUGUAY, VENEZUELA, MEXICO, ARUBA, NICARAGUA, PERU, PUERTO RICO, Curaçao, GUAM, GUATEMALA, GUYANA, HAITI, HONDURAS, JAMAICA, KOREA, SOUTH KOREA, PANAMA

**Document ID:** IK1200481

**Availability:** ISIS, Bus ISIS, FleetISIS, IsSIR

**Major System:** ENGINES

**Current Language:** English

**Other Languages:** [Français](#), [Español](#),

**Viewed:** 28373

**Revision:** 16

**Created:** 4/2/2010

**Last Modified:** 1/16/2019

**Author:** Bobby Christopher

[Less Info](#)
[Hide Details](#)

Coding Information

| Copy Link | Copy Relative Link | Bookmark                          | Add to Favorites | Print | Provide Feedback | Helpful | Not Helpful |
|-----------|--------------------|-----------------------------------|------------------|-------|------------------|---------|-------------|
|           |                    | <a href="#">View My Bookmarks</a> |                  |       |                  | 2477    | 1797        |

**Title: Aftertreatment Soot Level Reset after AFI, DPF or DOC Cleaning or Replacement**

**Applies To: EPA 07 MaxxForce® 11 & 13L Engines**

## CHANGE LOG

Dealers: Please refer to the change log text box below for recent changes to this article:

12/06/2019 - Updated based on feedback.  
 10/09/2015 - Added French and Spanish translations.  
 10/06/2015 - Updated Screenshot to show the Programming session is what you go to for reset request instead of Aftertreatment session.  
 05/22/2015 - Australia was added to the country coding.  
 04/09/2015 - Author updated for feedback purposes. Modified format. Added "ONLY EPA 2007 MaxxForce 11, 13L Engines" to description.

## DESCRIPTION

The soot level accumulator must be reset in the After Treatment Control Module (ACM) when one of the following aftertreatment components have been cleaned or replaced on **ONLY** EPA 2007 MaxxForce 11, 13L Engines:

- Diesel Particulate Filter (DPF) new or has been cleaned
- Diesel Oxidation Catalyst (DOC) new or has been cleaned
- EPA 07 MaxxForce 11 & 13L Engines Only - AFI cleaned or replaced



## SERVICE PROCEDURE

After the DOC and/or the DPF been cleaned or replaced follow the process below to reset the soot level:

1. Connect ServiceMaxx® to the vehicle.
2. Top Menu Go to Sessions (Figure 1).
3. Select Programming (Figure 1).
4. Select Service Interval Tab (Figure 2 -1).
5. Select Parameter - Aftertreatment Reset Request (Figure 2 -2).
6. Use Chart 1 to make the proper reset choice based on component and action
7. Select the choice from the drop down in the value field next to the parameter name (Figure 2- 3)
8. Select Program Engine after the selected reset choice has been made (Figure 2-4).

**Chart 1:**

| Component                           | Action                  | ServiceMaxx® Choice              |
|-------------------------------------|-------------------------|----------------------------------|
| Diesel Particulate Filter (DPF)     | Cleaned                 | DPF Cleaned                      |
| After Treatment Fuel Injector (AFI) | Cleaned or Replaced     | New or Cleaned AFT Fuel Injector |
| Diesel Particulate Filter (DPF)     | New Replaced            | New DPF Installed                |
| Diesel Oxidation Catalyst (DOC)     | New Replaced or Cleaned | New or Cleaned DOC               |

**Figure 1 - Menu Sessions - Programming****Figure 2 - Programming Session**

- 1 - Service Interval Tab
- 2 - Aftertreatment Reset Request
- 3 - Select Reset Action
- 4 - Select Program Engine

 Hide Details

Feedback Information

Viewed: 28372

Helpful: 2477

Not Helpful: 1797

No Feedback Found

Copyright © 2019 Navistar, Inc.