

GLOBAL SAFETY FIELD INVESTIGATIONS
DCS5066
URGENT - DISTRIBUTE IMMEDIATELY

Date: June 10, 2019

Subject: N192210560 - Service Update
Engine Calibration Torque Model Not Accurate

Models: 2019 Chevrolet Silverado 1500 (New Model)
2019-2020 GMC Sierra 1500 (New Model)
Equipped with Engine-Gas, 8 CYL, V8, 6.2L/Transmission-Auto 10
SPD (RPO L87/MQB)

To: All General Motors Dealers

General Motors is releasing Service Update N192210560 today. The total number of U.S. vehicles involved is approximately 50,652. Please see the attached bulletin for details.

Global Warranty Management (GWM)

The Required Field Action section on the Investigate Vehicle History (IVH) screen will be updated June 11, 2019. A list of involved vehicles in dealer new inventory is attached to this message. Please hold all warranty transactions until IVH has been updated.

END OF MESSAGE

GLOBAL SAFETY FIELD INVESTIGATIONS

Service Update

N192210560 Engine Calibration Torque Model Not Accurate



Release Date: June 2019

Revision: 00

Attention: This service update includes vehicles in dealer inventory and customer vehicles that return to the dealership for any reason. This bulletin will expire at the end of the involved vehicle's New Vehicle Limited Warranty period.

Make	Model	Model Year		RPO	Description
		From	To		
Chevrolet	Silverado 1500 (New Model)	2019	2019	L87/MQB	Engine-Gas, 8 CYL, V8, 6.2L/
GMC	Sierra 1500 (New Model)	2019	2020		Transmission-Auto 10 SPD

Involved vehicles are marked "open" on the Investigate Vehicle History screen in GM Global Warranty Management system. This site should always be checked to confirm vehicle involvement prior to beginning any required inspections and/or repairs.

Condition	Certain 2019 model year Chevrolet Silverado 1500 (New Model) and 2019-2020 model year GMC Sierra 1500 (New Model) vehicles may have a condition where the vehicle does not accelerate or decelerate but maintains speed after releasing the accelerator pedal for up to approximately 65 seconds. If the customer applies the brake pedal, the vehicle will stop as designed.
Correction	Reprogram the engine control module.

Parts

No parts are required for this repair.

Warranty Information

Labor Operation	Description	Labor Time	Trans. Type	Net Item
9104396*	Verified Module Software or Calibration Level: Module Programmed with Same Level Software or Calibration	0.2	ZFAT	N/A
9104397*	Engine Control Module Reprogramming with SPS	0.3		

* To avoid warranty transaction rejections, the SPS Warranty Claim Code must be entered when submitting this transaction. When more than one Warranty Claim Code is generated for a control module programming event, it is required to document all Warranty Claim Codes in the Correction field on the Job Card. Dealers must only enter one code in the "SPS Warranty Claim Code" field on the transaction, otherwise the transaction will reject.

Warranty Claim Code Information Retrieval

If the SPS Warranty Claim Code was not recorded on the Job Card, the code can be retrieved in the SPS system as follows:

- Open TIS on the computer used to program the vehicle
- Select and start SPS
- Select Settings
- Select the Warranty Claim Code tab

The VIN, Warranty Claim Code and Date/Time will be listed on a roster of recent programming events. If the code is retrievable, dealers should resubmit the transaction making sure to include the code in the SPS Warranty Claim Code field.

Service Procedure

Note: Carefully read and follow the instructions below.

- Ensure the programming tool is equipped with the latest software and is securely connected to the data link connector. If there is an interruption during programming, programming failure or control module damage may occur.
- Stable battery voltage is critical during programming. Any fluctuation, spiking, over voltage or loss of voltage will interrupt programming. Install a GM Authorized Programming Support Tool to maintain system voltage. Refer to www.gmdesolutions.com for further information. If not available, connect a fully charged 12V jumper or booster pack disconnected from the AC voltage supply. DO NOT connect a battery charger.
- Turn OFF or disable systems that may put a load on the vehicles battery such as; interior lights, exterior lights (including daytime running lights), HVAC, radio, etc.

Service Update

N192210560 Engine Calibration Torque Model Not Accurate



- Clear DTCs after programming is complete. Clearing powertrain DTCs will set the Inspection/Maintenance (I/M) system status indicators to NO.

5164840

Note: If the Same Calibration/Software Warning is noted on the SPS Summary screen, record the warranty claim code (WCC) and select OK and follow screen instructions. After a successful programming event, the WCC is located in the Service Programming System dialogue box of the SPS Summary screen. No further action is required. Refer to the Warranty section of the bulletin.

1. Reprogram the Engine Control Module. Refer to *K20 Engine Control Module: Programming and Setup* in SI.

5164843

2. Record SPS Warranty Claim Code on job card for warranty transaction submission.

Dealer Responsibility

Whenever a vehicle subject to this service update enters your vehicle inventory or is in your facility for service in the future, and the vehicle is still covered under the New Vehicle Limited Warranty, you must take the steps necessary to be sure the service update correction has been made before selling or releasing the vehicle.

All new, used, GM Certified Used, courtesy transportation vehicles, dealer shuttle vehicles, etc. in dealers' possession and subject to this bulletin must be held and inspected/repared per the service procedure of this bulletin before customers take possession of these vehicles. Involved vehicles must be held and not delivered to customers, dealer-traded, released to auction, used for demonstration, or any other purpose.

Service Update

N192210560 Engine Calibration Torque Model Not Accurate



All GM Certified Used vehicles currently in the dealers' inventory within the Certified Pre-Owned Inventory System (CPOIS) will be de-certified and must be held and remedied per the service procedure in this bulletin. Upon submitting an accepted/paid warranty transaction in the Global Warranty Management (GWM) system, the vehicle can be re-certified for sale within the CPOIS system, or once again be used in the CTP program.

GM bulletins are intended for use by professional technicians, NOT a "do-it-yourselfer". They are written to inform these technicians of conditions that may occur on some vehicles, or to provide information that could assist in the proper service of a vehicle. Properly trained technicians have the tools, equipment, safety instructions, and know-how to do a job properly and safely. If a condition is described, **DO NOT** assume that the bulletin applies to your vehicle, or that your vehicle will have that condition. See your dealer for information on whether your vehicle may benefit from the information.



**We Support
Voluntary Technician
Certification**