

R.O. No.

2020

Stock No.



Audi Pre-Delivery Inspection

Dealer Number

| VIN Road test mileage out | Road test mileage in |
|--|--|
| Reminders | |
| ► All items must be completed prior to customer delivery by a cert | tified Audi technician |
| ► Audi recommends using an Audi approved battery charger to pro | |
| ► ALL PDI function tests must be run in Guided Fault Finding (GFI | |
| ▶ It is advised to start ODIS with the engine running to enable all | 5F Test Plans in GFF |
| ▶ For items marked with *, please refer to the PDI Technician Refe | rence Document posted on ServiceNet for additional information |
| ► For items marked with **, follow instructions for stock inventor | y vehicle |
| Vehicle Preparation | Interior |
| ☐ Check Elsa for open campaigns and updates | ☐ Verify operation of all seat belts and latches |
| ☐ Verify Audi phone box customer registration form is present | ☐ Check operation of window, lock, and seat controls* |
| in vehicle and add the serial number from Elsa (if equipped). See TSB 2051720 | ☐ Inspect mirrors for proper operation* |
| _ | ☐ Check rear view mirror operation* |
| Perform any open campaigns* Perform diagnostic work* | ☐ Verify operation of all interior lights |
| ☐ Install front license plate carrier (if necessary)* | ☐ Verify SOS button is green and Roadside assistance button LED will remain off. Reference TSB 2052299 if issues occur |
| | ☐ Verify operation of heated seats |
| Exterior | ☐ Verify operation of heated rear seats (if equipped) |
| Check all key buttons and features* | ☐ Verify operation of ventilated seats (if equipped) |
| ☐ Inspect exterior for damage, dings, dents and surface scratches. Report and repair any damage before delivery to the customer | ☐ Verify proper operation of climate control* |
| | ☐ Inspect operation of all power outlets* |
| | $\hfill \Box$ Verify the glove compartment opens and closes properly |
| Lighting and Windshield | Check panoramic sunroof and sunshade operation* |
| ☐ Test exterior lighting functions | Verify operation of front Passenger Occupant Detection |
| ☐ Test windshield washers. Correct aim if necessary* | System |
| Turnel Inspection | Settings |
| Trunk Inspection | ☐ Verify operation of MMI® touch |
| ☐ Verify trunk is operational☐ Verify operation of emergency release handle | ☐ Set Time source setting to "GPS" and set Auto daylight savings time to "on."* |
| ☐ Install wheel bolt cover removal tool from PDI kit into trunk tool kit* | Set Time to "Automatic setting" and "Automatic time zone" |
| | ☐ Verify and set language and measurement units* |
| ☐ Verify tool kit is installed securely in luggage compartment | ☐ Verify Speech Dialog System is operating* |
| ☐ Set spare tire pressure* | Set "Entertain. Fad." in Parking aid to an audible level* |
| ☐ Check battery clamps for proper torque* | Set "Music volume while parking" to medium* |



2020

Audi Pre-Delivery Inspection

| Settings (continued) | Driving Performance (continued) |
|--|--|
| Set dealership location in navigation (if equipped)* | Check steering/tire alignment |
| ☐ Turn off Manual Speed Warning (if equipped)* | Check for squeaks, rattles and wind noise. Repair any squeaks, rattles or wind noises before delivery to the cus- |
| Media / Radio / SAT | tomer |
| Verify operation of aux. input | Calibrate rear view mirror* |
| ☐ Insert SD card and test function of all slots | ☐ Verify quality of radio reception in AM/FM/SiriusXM® bands |
| ☐ Verify HD Radio is turned "off"* | Driver Assistance |
| Ad: | |
| Audi connect® (USA ONLY) (if equipped) | ☐ Verify cruise control/ACC with Stop & Go functionality (if equipped) |
| Turn on the Wi-Fi® hotspot (if equipped)* | ☐ Verify Audi side assist functionality (if equipped) |
| Check Wi-Fi® hotspot visibility. No data available at PDI (if equipped)* | ☐ Verify Audi active lane assist functionality (if equipped) |
| ☐ Enable satellite map view for navigation (if equipped)* | ☐ Verify operation of parking system (if equipped)* |
| | ☐ Verify all vehicle Head-up display functionality (if equipped)* |
| On-Hoist Inspection | Activate NAV and follow directions back to dealership (if |
| Remove transport suspension blocks (follow ELSA instruction) | equipped) |
| Check steering, boots, brake system, hoses, tires and wheels for damage | Convertible Functionality (if equipped) |
| Check underside of vehicle for fluid leaks and loose components | ☐ Test operation of power folding top* |
| ☐ Install wheel locks (if equipped) | ☐ Verify convertible top manual closing tools are present |
| ☐ Install wheel bolt covers and center caps as supplied* | |
| ☐ Inspect wheel bolts for proper torque* | Post-Road Test Inspection |
| Set and store tire pressures for either sold vehicle OR stock inventory vehicle* | ☐ Interrogate fault memory and upload Diagnostic Log to GFF Paperless Server |
| | Check service interval and verify correct interval is displayed |
| Driving Performance | ☐ Check engine oil level* |
| Check horn operation | ☐ Check all fluid levels and top off if necessary |
| ☐ Verify hold and release of electronic parking brake☐ Verify engine Start-Stop System functionality* | ☐ Ensure the yellow tire pressure tag is installed on the steering wheel |
| ☐ Verify engine performance and acceleration* | Apply 30 Day Inventory Maintenance Sticker** |
| ☐ Verify transmission operation, including shift paddles ☐ Test drive vehicle applying brakes several times* | ☐ Install showroom charger to ensure battery remains charged at all times** |
| Technician I certify that all operations have been completed and this veh Quality Standards, and has met the standards for Perfect Deli | icle has been prepared in accordance with Audi Procedures and very. st 8 of VIN Completion Date |
| /// recument signature | //// Completion pate //////////////////////////////////// |
| | ·/////// |