

2021

A7/S7/RS 7

Audi Pre-Delivery Inspection

| Stock No. De | Dealer Number | | R.O. No. | |
|--|--------------------------------------|--|--|--|
| VIN Road test mileage out | | Road test mileage in | | |
| Reminders | | | | |
| ▶ All items must be completed prior to custo | omer delivery by a cer | tified Audi technician | | |
| ► Audi recommends using an Audi approved | battery charger to pr | event excessive batte | ry discharge during inspection | |
| ► Guided Fault Finding must be used, session | n must be completed | and sent to GFF Pape | erless | |
| ► Total PDI Test must be completed prior to | any other work involv | ring the scan tool (spe | ecial function tab -> Total PDI Test) | |
| ► Start Guided Fault Finding with the engine | running to ensure co | ontrol modules in trai | nsport mode are identified | |
| ► For items marked with *, please refer to th | e PDI Technician Refe | erence Document post | ted on ServiceNet for additional information | |
| ► For items marked with **, follow instruction | | - | | |
| | | - | | |
| Vehicle Preparation | | Trunk Inspection (continued) | | |
| Check Elsa for open campaigns and updates | | Check battery clamps for proper torque* | | |
| Verify Audi phone box customer registration form is present in vehicle and add the serial number from Elsa (if equipped). See TSB 2051720 □ Perform any open campaigns* | | ☐ Place one PR Number Label in the Warranty and Mainte- nance Book inside front cover and one on the Rear Panel Sill Frame under the luggage compartment floor, if not already | | |
| | | there* | | |
| Perform diagnostics work* | | | | |
| ☐ Install front license plate carrier (if necessary)* | | Interior | | |
| | | ☐ Verify operation of all seat belts and latches | | |
| Exterior | | | of window, lock, and seat controls* | |
| ☐ Check all key buttons and features* | | ☐ Inspect mirrors for proper operation* | | |
| Check all doors for proper power closing (if equipped)* | | Check rear view mirror operation* | | |
| ☐ Inspect exterior for damage, dings, de | | _ , | of all interior lights | |
| scratches. Report and repair any damage the customer | | ☐ Check heated st DTC B153813) | eering wheel (if equipped, otherwise, ignore | |
| Lighting and Windshield | | ☐ Verify operation heated/ventilated and massaging seats (if equipped)* | | |
| ☐ Test exterior lighting functions | | ☐ Verify operation | of manual folding 2nd row | |
| ☐ Test windshield washers (and headlight w | vashers if | ☐ Verify proper op | eration of climate control* | |
| equipped) Correct aim if necessary* | | ☐ Inspect operation | on of all power outlets* | |
| | | ☐ Check sunroof and sunshade operation* | | |
| Trunk Inspection Verify trunk is operational | | ☐ Verify operation of front Passenger Occupant Detection System | | |
| | | | | ☐ Install wheel bolt cover removal tool from PDI kit into trunk tool kit*☐ Verify tool kit is installed securely in luggage compartment |
| ☐ Verify operation | of power rear sunshade (if equipped) | | | |

☐ Set spare tire pressure (if equipped)*



2021

A7/S7/RS 7

Audi Pre-Delivery Inspection

| Settings | Driving Performance (continued) | | |
|--|---|--|--|
| $\hfill \Box$ Verify operation of MMI $^{\ensuremath{@}}$ touch screens, upper and lower | ☐ Verify rear spoiler functionality (if equipped) | | |
| Set Time source setting to "GPS" and set Auto daylight sav- | ☐ Check steering/tire alignment | | |
| ings time to "on"* | Check for squeaks, rattles and wind noise. Repair any squeaks, rattles or wind noises before delivery to the cus- tomer | | |
| ☐ Verify and set language and measurement units* | | | |
| Verify Speech Dialog System is operating* | Calibrate rear view mirror* | | |
| Set "Music volume while parking" to medium* | ☐ Verify quality of radio reception in AM/FM/SiriusXM® bands | | |
| Set dealership location in navigation* | verify quality of radio reception in API/119/3inusXPI- bands | | |
| Turn off Manual Speed Warning (if equipped)* | Driver Assistance | | |
| Media / Radio / SAT | ☐ Verify all cruise control functions | | |
| ☐ Verify operation of all USB ports | □ Verify cruise control/ACC with Stop & Go functionality (if equipped), which includes the following:□ Adaptive Cruise Assist | | |
| ☐ Verify operation of aux. input | | | |
| ☐ Verify operation of CD/DVD player (if equipped) | ☐ Turn Assist ☐ Intersection Assistant ☐ Traffic Jam Assist | | |
| ☐ Insert SD card and test function of slot | | | |
| Program the presets to local stations | | | |
| ☐ Verify HD Radio is turned "off"* | ☐ Predictive Efficiency Assist | | |
| | Active lane assist with emergency assistant | | |
| On-Hoist Inspection | ☐ Traffic sign recognition | | |
| Remove transport suspension blocks (follow ELSA instruction). For vehicles with sport suspension 1BE: Ensure transport blocks under dust boot are removed | ☐ Verify Audi side assist functionality Pre sense® rear (if equipped) | | |
| Remove locking elements on front axle suspension struts | ☐ Verify operation of night vision camera (if equipped) | | |
| (For vehicles with sport suspension 1BE)* | ☐ Verify operation of parking system* | | |
| Check steering, boots, brake system, hoses, tires and wheels for damage | ☐ Verify all vehicle Head-up display functionality (if equipped)* | | |
| Check underside of vehicle for fluid leaks and loose components | ☐ Verify operation of High-beam assistant (if equipped)☐ Activate NAV and follow directions back to dealership | | |
| ☐ Install wheel locks (if equipped) | | | |
| ☐ Install wheel bolt covers and center caps as supplied* | Post-Road Test Inspection | | |
| ☐ Inspect wheel bolts for proper torque* | ☐ Verify SOS button is green and Roadside assistance button LED will remain off | | |
| Set and store tire pressures for either sold vehicle OR stock inventory vehicle* | ☐ It may take up to 20 minutes for the emergency call system to activate (LED turns green) after flight/transport mode deactivation | | |
| Driving Performance | ☐ The vehicle must not be delivered to the customer if the | | |
| Check horn operation | emergency call function has not been successfully activated (LED lights up in green) Interrogate fault memory and upload diagnostic log to GFF Paperless Server Check service interval and verify correct interval is displayed | | |
| ☐ Verify hold and release of electronic parking brake | | | |
| ☐ Verify engine Start-Stop System functionality* | | | |
| ☐ Verify engine performance and acceleration* | | | |
| $\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ $ | ☐ Check engine oil level* | | |
| ☐ Test drive vehicle applying brakes several times* | ☐ Check all fluid levels and top off if necessary | | |
| ☐ Check adaptive air suspension in all positions (if equipped) | | | |

Effective 6-30-2020-US Version 1.0



2021

A7/S7/RS 7

Audi Pre-Delivery Inspection

| Post-Road lest Inspection (continued) | Audi connect® (USA UNLY) | | | | |
|--|--|---------------------------|--|--|--|
| $\hfill \square$ Ensure the yellow tire pressure tag is installed on the steer- | ☐ Turn on the Wi-Fi® hotspot (if equipped)* | | | | |
| ing wheel | ☐ Check Wi-Fi® hotspot visibility. No data available at PDI due to dealer demo mode (if equipped)* | | | | |
| Apply 30 Day Inventory Maintenance Sticker** | | | | | |
| ☐ Install showroom charger to ensure battery remains charged at all times** | ☐ Enable satellite map view for | navigation (if equipped)* | | | |
| | | ·/////// | | | |
| //// Technician | | <i>'</i> //// | | | |
| I certify that all operations have been completed and this vehicle has been prepared in accordance with Audi Procedures and Quality Standards, and has met the standards for Perfect Delivery. | | | | | |
| Technician Signature | ast 8 of VIN | Completion Date | | | |
| <i>\\\\\\\</i> | | \\\\\\\\ | | | |