

2021

Q3

Audi Pre-Delivery Inspection

Stock No.

Dealer Number

R.O. No.

VIN

Road test mileage out

Road test mileage in

Reminders

- ▶ All items must be completed prior to customer delivery by a certified Audi technician
- ▶ Audi recommends using an Audi approved battery charger to prevent excessive battery discharge during inspection
- ▶ Guided Fault Finding must be used, session must be completed and sent to GFF Paperless
- ▶ Total PDI Test must be completed prior to any other work involving the scan tool (special function tab -> Total PDI Test)
- ▶ Start Guided Fault Finding with the engine running to ensure control modules in transport mode are identified
- ▶ For items marked with *, please refer to the PDI Technician Reference Document posted on ServiceNet for additional information
- ▶ For items marked with **, follow instructions for stock inventory vehicle

Vehicle Preparation

- Check Elsa for open campaigns and updates
- Verify Audi phone box customer registration form is present in vehicle and add the serial number, [FCC ID](#), and [Model](#) from Elsa (if equipped). See TSB 2051720
- Perform any open campaigns*
- Perform diagnostic work*
- Install front license plate carrier (if necessary)*

Exterior

- Check all key buttons and features*
- Inspect exterior for damage, dings, dents and surface scratches. Report and repair any damage **before** delivery to the customer

Lighting and Windshield

- Test exterior lighting functions
- Test windshield washers (and headlight washers if equipped). Correct aim if necessary*

Trunk Inspection

- Verify power tailgate is operational and set default opening height*
- Install wheel bolt cover removal tool from PDI kit into trunk tool kit*
- Verify tool kit is installed securely in luggage compartment
- Set spare tire pressure*
- Check battery clamps for proper torque*

Interior

- Verify operation of all seat belts and latches
- Check operation of window, lock, and seat controls*
- Inspect mirrors for proper operation*
- Check rear view mirror operation*
- Verify operation of all interior lights
- Verify operation heated seats
- Verify proper operation of climate control*
- Inspect operation of all power outlets*
- Check panoramic sunroof and sunshade operation*
- Verify the glove compartment opens and closes properly
- Verify operation of front Passenger Occupant Detection System

Settings

- Set Time source setting to “GPS” and set Auto daylight savings time to “on.” (if equipped with navigation)*
- Set “Entertain. Fad.” in parking aid to an audible level (if equipped)*
- Set Time to “Automatic setting” and “automatic time zone”
- Verify and set language and measurement units*
- Verify Speech Dialog System is operating*
- Set dealership location in navigation (if equipped)*

Media / Radio / SAT

- Verify operation of aux input
- Insert SD card and test function of slot



2021

Q3

Audi Pre-Delivery Inspection

Media / Radio / SAT (continued)

- Verify HD Radio is turned "off"*
- Confirm SiriusXM is on and in an active state (can scroll through channels and hear music)
- Verify operation of USB data and charge (2 in front), USB charge (2 in rear)

Audi connect® (USA ONLY) (if equipped)

- Turn on the Wi-Fi® hotspot (if equipped)*
- Check Wi-Fi® hotspot visibility. No data available at PDI (if equipped)*
- Enable satellite map view for navigation (if equipped)*

On-Hoist Inspection

- Remove transport suspension blocks (follow ELSA instruction)
- Check steering, boots, brake system, hoses, tires and wheels for damage
- Check underside of vehicle for fluid leaks and loose components
- Install wheel locks (if equipped)
- Install wheel bolt covers and center caps as supplied*
- Inspect wheel bolts for proper torque*
- Set and store tire pressures for either sold vehicle **OR** stock inventory vehicle*

Driving Performance

- Check horn operation
- Verify hold and release of electronic parking brake
- Verify engine Start-Stop System functionality*
- Verify engine performance and acceleration*
- Verify transmission operation, including shift paddles (if equipped)
- Test drive vehicle applying brakes several times*

Driving Performance (continued)

- Check steering/tire alignment
- Check for squeaks, rattles and wind noise. Repair any squeaks, rattles or wind noises **before** delivery to the customer
- Calibrate rear view mirror*
- Verify quality of radio reception in AM/FM/SiriusXM® bands (if equipped)

Driver Assistance

- Verify all cruise control functions
- Verify adaptive cruise control with Stop & Go functionality (if equipped)
- Audi active lane assist (if equipped)
- Verify Audi side assist functionality (if equipped)
- Verify operation of Topview camera (if equipped)
- Verify operation of rearview camera
- Verify operation of Park steering assist (if equipped)
- Verify operation of Audi parking system plus with rear cross traffic assist (if equipped)*
- Activate navigation and follow directions back to dealership (if equipped)

Post-Road Test Inspection

- Interrogate fault memory and upload Diagnostic Log to GFF Paperless Server
- Check service interval and verify correct interval is displayed
- Check engine oil level*
- Check all fluid levels and top off if necessary
- Ensure the yellow tire pressure tag is installed on the steering wheel
- Apply 30 Day Inventory Maintenance Sticker**
- Install showroom charger to ensure battery remains charged at all times**


Technician

I certify that all operations have been completed and this vehicle has been prepared in accordance with Audi Procedures and Quality Standards, and has met the standards for Perfect Delivery.

Technician Signature

Last 8 of VIN

Completion Date



Audi Phone Box-Equipped Vehicles

Operation of the Audi Phone Box is subject to the following requirements of the Federal Communications Commission:

This is a CONSUMER device.


BEFORE USE, you MUST REGISTER THIS DEVICE with your wireless provider and have your provider's consent. Most wireless providers consent to the use of signal boosters. Some providers may not consent to the use of this device on their network. If you are unsure, contact your service provider.

You MUST operate this device with approved antennas and cables as specified by the manufacturer. Antennas MUST be installed at least 20 cm (8 inches) from any person.

You MUST cease operating this device immediately if requested by the FCC or a licensed wireless service provider.

WARNING. E911 location information may not be provided or may be inaccurate for calls served by using this device.

Make # _____ FKW _____
Model # _____
Serial # _____ FKW - _____
FCC ID _____



This Signal Booster fulfills the FCC requirements for the Network Protection Standard (NPS). It incorporates features to prevent harmful interference to wireless networks like:

- ▶ Anti-oscillation to detect and mitigate any unintended oscillations in uplink and downlink frequency bands,
- ▶ Adaptive gain control with self-monitoring and to power down automatically as approaching any affected base station,
- ▶ Uplink Inactivity to shut down the transmit amplifiers if not serving an active device connection.

This Signal Booster includes features to prevent harmful interference. These features are enabled and operating at all times the signal booster is in use, they may not be deactivated by the operator.
