

Service Bulletin

INFORMATION

Brand:	Model:	Model Year:		VIN:		Engine	Transmission:
		from	to	from	to	Engine:	
Buick	Encore	2013	2020				
Chevrolet	Cruze	2013	2015		_	1.4L (LUV) and 1.8L (LWE)	_
	Cruze (VIN P)	2016	2016				
	Sonic	2013	2020				
	Trax	2013	2020				


Subject: Information on Proper Oil Filter Usage

Involved Region or Country	North America, South America and Israel	
Information	The purpose of this bulletin is to inform technicians and dealership personnel that the above models and model year vehicles, equipped with the 1.4L turbocharged engine and 1.8L engine, use two different suppliers for the oil filter housing, which results in two different oil filters being used. Important: It is very important to use the correct oil filter for the oil filter housing application.	

Important: These engines are affected by an oil filter and filter housing supplier change mid production (Hengst to UFI). The oil filter elements for the housings are not interchangeable. It is critical to confirm the correct oil filter is being used, otherwise the oil filter may be bypassed entirely. The VIN alone is not sufficient for oil filter application confirmation.

Note: This material is intended only as a guide. Refer to the appropriate catalog for specific vehicle application.

ACDelco PF2257G



4978033



4990879

	Identification
1	No Ribs
2	Felt style gasket/seal
3	Supplier Name: Hengst
4	Bypass valve in housing

ACDelco PF2263G



4982739

	Identification
1	Bypass valve in filter
2	4 spacers/Ribs
3	O-ring style gasket/seal
4	Supplier Name: UFI



4991024

	Identification	
1	Cap: Dark Brown	
2	Supplier Name: UFI	
3	Circumference: Ribbed	
USE PF2263G Filter		



4991019

	Identification	
1	Cap: Black	
2	Supplier Name: Hengst	
3	Circumference: Smooth	
USE PF2257G Filter		

Additional Information

Access training at WWW.ACDelcoTraining.com. Visit www. ACDelcoTechonnect.com.

Parts Information

For part number and usage, see Filter Kit, Oil in Group 01.836 in the electronic part catalog (EPC).

Version	4
Modified	July 28, 2017 – Removed the 2017-2018 Cruze (VIN B) from Model section. February 27, 2018 – Added the 1.8L Engine and oil filter difference information.
	August 13, 2020 – Added the 2019-2020 Model Years to the Encore, Sonic and Trax.

GM bulletins are intended for use by professional technicians, NOT a "do-it-yourselfer". They are written to inform these technicians of conditions that may occur on some vehicles, or to provide information that could assist in the proper service of a vehicle. Properly trained technicians have the equipment, tools, safety instructions, and know-how to do a job properly and safely. If a condition is described, <u>DO NOT</u> assume that the bulletin applies to your vehicle, or that your vehicle will have that condition. See your GM dealer for information on whether your vehicle may benefit from the information.



WE SUPPORT VOLUNTARY TECHNICIAN CERTIFICATION