

# TECHNICAL TOPICS

## ELECTRICAL



### Intermittent Passive Entry Operation

20-21MY L663 Defender

#### Customer Voice:

- Intermittently, the passive unlock feature does not work unless the smart key is in the customer's hand.

#### Technical Description:

- Due to poor signal strength the passive entry feature may not function intermittently

#### Status:

- JLRTB02076NAS1 will provide instructions to relocate a new RF Receiver behind the left D-pillar trim.
- Prior to installation a link lead will need to be assembled, please refer to TOPIx Workshop Manual section 418-02: Wiring Harnesses – Description & Operation Wiring Harness to review JLR approved wiring harness repair methods.
- **Publication of JLRTB02076NAS1 has been delayed due to part availability.**
- Please raise a TA until the bulletin is published.

