TECHNICAL TOPICS BODY/CHASSIS





Second Row Seat Lower Level Parts

Customer Voice:

A customer may report a ratcheting sound when folding/unfolding the second row seats.

Technical Description:

This could be caused by a poor seat pivot or fore/aft adjustment.

Status:

- A lower level service kit has been released to repair this concern without the need to replace the seat frame assembly.
- The Workshop procedure has been updated, Section 501-10 Seating > General Procedures > Second Row Seat Recline Mechanism.
- Service kit part numbers LR156813, LR156814, LR156815 and LR156816 are now available and used be used to conduct a lower level repair whenever possible.

15 – 19MY Discovery Sport 17MY – Onwards Discovery 20MY – Onwards Defender











