



(Back Office Only) Mack Chassis - Without Automated Manual Transmission - Cruise Control Inoperative



> Internal Content

First would be to check the build date on the truck in Volvo Data Administration (VDA). Once it is confirmed to be built on or after W1707 you can continue checking the switch installation.

Confirm that the Vehicle Electronic Control Unit (VECU) is missing pin A-7 (Green Connector). That is where the wire from the redundant switch should be located. If missing, make the following changes in VDA then have the dealer program the VECU. That will remove the functionality from the VECU and allow cruise control to work properly.

ECB=21

CVM=0

FBK=0

RCR=0

RCQ=0

QPE=0



Tags

[mack](#)

Related links and attachments

No links or attachments available



Feedback

[Give feedback](#)

to help improve the content of this article