



## STAR ONLINE PUBLICATION



**Case Number:** S2108000161

**Release Date:** July 2021

**Symptom/Vehicle Issue:** Cluster Service Air Suspension Message, DTC C1526-11 Left Rear Ride Height Sensor - Circuit Short To Ground

**Customer Complaint/Technician Observation:** Owner complains of a cluster warning message "Service Air Suspension". Technician observed the vehicle is setting DTC C1526-11 Left Rear Ride Height Sensor Circuit Short To Ground.

**Repair Procedure:** Inspection of the harness routing at the rear cradle, fuel tank location. Ensure the harness is secure and not contacting any bracket edges as shown. Repair any harness contact areas and isolate and secure the harness as needed to complete.



This document does not authorize warranty repairs. This communication documents a record of past experiences. STAR Online does not provide any conclusions about what is wrong with the vehicle. Rather, it captures all previous cases known that appear to be similar or related to the vehicle symptom / condition. You are the expert, and you are responsible for deciding on the appropriate course of action.

**Contact STAR Center, or your Technical Assistance Center Via TechCONNECT or eCONTACT ticket if no solution is found**