

TECHNICAL TOPICS

Powertrain



AJ20-P6 Turbo Coolant Pipe O Ring Repair

20-23MY Defender
19-22MY Range Rover, Range Rover Sport

Customer Voice:

Customer concern will be a low coolant light on or a coolant leak

Technical Description:

If there's an issue detected with either of the O rings on the turbo coolant pipes, it is requested to replace both the feed and return pipe, even if only one has an issue.

Status:

After replacing both pipes it is requested to please inspect the heater hose referring to "Image_2" in the SSM.

If the heater hose is not in the correct position, please replace the heater hose. Make sure the new heater hose is orientated correctly.

If range Rover or Range Rover Sport, please take photographs and attach them to an ePQR before replacing it.

Refer to SSM 75747

