

TECHNICAL TOPICS

Powertrain



V8 T/C 4.4 Restricted Performance/Torque Derate, Failed ECO Start
Possible MIL

22MY New Range Rover

Customer Voice:

Customer concern will be a loss of performance/torque derate, slow to accelerate.
Failed eco-starts.

Technical Description:

You will have the presence of DTC P0191-85 stored on PCM (P01BF-85 on both PCMs).

Status:

Do NOT replace the sensor unless electrical checks show genuine fault with part.
Ensure PCM software is up to date. Clear DTCs and retest. Return to customer. There is the possibility that a key cycle will remove torque derate.

Please raise a TA specifying "Customer symptoms of torque derate and/or failed eco-starts with P0191-85 or P01BF-85 stored in PCM" and provide a session file.

Refer to SSM 75741

