

Deployable Sidestep - No operation

22-23MY New Range Rover, New Range Rover Sport

Customer Voice:

- Customer states that the deployable side steps are not operational

Technical Description:

- This has occurred after CCF As-Built has been loaded into the vehicle. Loading the CCF as-built has removed the Deployable Sidestep option from the CCF

Status:

- Please follow step 8 completely in the accessory fitting instructions for Deployable Side Steps (Electrical Only) only after all other CCF work has been completed.
- SSM75802 has been released for this concern

