





GROUP	MODEL
Electrical	2018-2023MY Stinger (CK)
NUMBER	DATE
PS738	November 2022



TECHNICAL OPERATIONS

SUBJECT: VARIANT CODING AFTER MDPS/EPS REPLACEMENT

This Pitstop provides information to perform variant coding on some 2018-2023MY Stinger (CK) vehicles, after replacement of an MDPS and/or EPS unit. The selections on KGIS do not match those on the KDS. Follow the procedure below to perform variant coding on a newly replaced MDPS and/or EPS unit.

KGIS:	KDS:
Instructions state to perform "ESP Type Recognition"	No option for "ESP Type", only "MDPS Tuning Data Setting (Backup and Write)"
	

Using KDS:

1. Select 'MDPS Tuning Data Setting (Backup and Write)'.
2. Select 'OK'.
3. Follow the prompts to the specification setting, then select 'C2'.
4. This will take you to the Variant Coding screen where you can select the correct vehicle specifications.
5. Complete Variant Coding.

