

## MALFUNCTION INDICATOR LAMP(MIL) ON WITH DIAGNOSTIC TROUBLE CODE P0456-00

### Customer Voice:

- MIL lamp on the instrument cluster

### Technical Description:

- DTC P0456-00 stored in the Powertrain Control Module (PCM).
- Will not have any effect on vehicle operation.

### Status:

- Vacuum test both purge valves, please make sure they hold vacuum.
- Please move all lines and hoses while performing a smoke leak test.
- If both symptoms are still present after performing the above test and workflow in TOPIx for the code, please raise a Technical Assistance (TA) for further guidance with diagnosis. The TA must be directed to PTS\_200
- The relevant JLR Engineering teams are investigating this concern. Following the Service Request section of this SSM will assist Engineering in conducting the required investigation.

Refer to SSM 76148

### Range Rover

- 22-23MY Range Rover- NC10 ONLY
- 23-23MY RR Sport – NC10 ONLY

