



Bulletin No.: PIC6511A
Published date: 07/31/2024

Preliminary Information

PIC6511A Diagnostic Tip - Unwanted Park Assist Indication


Models

| Brand: | Model: | Model Years: | VIN: from to | Engine: | Transmissions: |
|---------------|--------------------|---------------------|-------------------------|----------------|-----------------------|
| Cadillac | Lyriq | 2023 - 2024 | All | All | All |
| Chevrolet | Traverse (All New) | 2024 | All | All | LK0 |
| GMC | Acadia | 2024 | All | All | LK0 |

| | |
|-----------------------------------|--|
| Involved Region or Country | North America |
| Condition | A customer may comment that the Park Assist will indicate an object detected intermittently from either the left or right front middle sensors. |
| Cause | Possible interference from front License Plate Frame. |

Correction:

Example of Park Assist indicator.





- 1. Check for a License Plate Frame to be installed on the front License Plate similar to the picture above.**
- 2. If a License Plate Frame is present, remove the frame and re-evaluate for the concern.**
- 3. If the concern is no longer present, do not re-install the License Plate Frame.**
- 4. If the concern is still present, refer to normal SI Diagnostics.**

Warranty Information

Version History

| | |
|-----------------|--|
| Version | 2 |
| Modified | 07/12/2023 - Created on. 07/31/2024 - Updated Models. |