



Bulletin No.: PIC6569
Published date: 08/27/2024

Preliminary Information

PIC6569 Performance Data Recorder Inoperative with a Battery Draw and a U1652 Setting


Models

Brand: Chevrolet **Model:** Corvette **Model Years:** 2024 - 2025 **VIN:** All **Engine:** All **Transmissions:** All

Involved Region or Country	North America
Additional RPO	UQT - Vehicle Performance Data Recorder
Condition	Some customers may comment about either a Performance Data Recorder (PDR) that is inoperative, or possibly, a dead battery. The concern will be accompanied with a U1652 set in the Serial Data Gateway Module.

Correction:

The customer will either have a PDR application that will not open on the radio display screen, or it will open, but it will be blank. A welcome screen may also be displayed when the PDR app icon is pressed. This welcome screen can be seen in the picture below.



If this issue is encountered, dealership technicians are to simply press the Home button on the radio display to confirm that the system will exit the PDR function and return to the radio home screen. If so, that confirms the issue is being caused by a software anomaly in the K161 Performance Data Recorder Module, which may not allow all the internal functions to properly initialize during startup. Engineering is currently investigating this concern.

Recommendations / Instructions

Dealership technicians are to perform a 12v global reset on the battery for a full 5 minutes on the vehicle. To properly perform this, remove the battery cables from the 12v battery and hold / secure them together to discharge any stored energy in the vehicle. This will return the normal PDR functionality. The issue is very unlikely to return at that point in time. If a battery reset does not fully resolve this condition, continue using SI diagnostics as needed.


Warranty Information

For vehicles repaired under the Bumper-to-Bumper coverage (Canada Base Warranty coverage), use the following labor operation. Reference the Applicable Warranties section of Investigate Vehicle History (IVH) for coverage information.

Labor Operation	Description	Labor Time
0541459	Black screen with audio - Customer Concern Not Duplicated (CCND)	0.3 Hr.

Version History

Version	1
Modified	08-27-2024 - Created on.

 GM Global Brands

© 2024 General Motors. All Rights Reserved.