



Bulletin No.: PIT6202B

Published date: 09/13/2024

Preliminary Information

PIT6202B Hood Ajar Message Illuminated On The IPC With DTC B1C8D, B1C8C, B1C80, B1C81, P257F

Models

| Brand: | Model: | Model Years: | VIN: from to | Engine: | Transmissions: |
|---------------|------------------|---------------------|-------------------------|----------------|-----------------------|
| Chevrolet | Silverado EV RST | 2024 | All | All | All |
| GMC | Hummer EV | 2022 - 2025 | All | All | All |
| GMC | Hummer EV SUV | 2024 - 2025 | All | All | All |
| GMC | Sierra Denali EV | 2024 | All | All | All |

| | |
|-----------------------------------|---|
| Involved Region or Country | North America |
| Additional Options (RPO) | AHV Power Hood Control |
| Condition | A customer/driver could see a “ Hood Ajar ” message that displays on the IPC along with one or more of the following DTC's: B1C8D, B1C8C, B1C80, B1C81, P257F. |
| Cause | The eTrunk has lost its learned position. |

Correction:


Technicians are instructed to remove and reinstall the K241 Powertrain Compartment Cover Module (F54UA) fuse and then perform a relearn of the Power Front Compartment Module by following Document ID: 6616845 in Service Information.

The eTrunk is designed to be opened and closed using either of the three methods:


- Key Fob
- Switch on the instrument panel to the left of the steering wheel
- The touchpad right of center of the front fascia (shown below for different models)

NOTE: When using the Key fob or the switch in the Instrument panel to close the hood, press and hold the hood open button until the hood closes. Releasing the button will stop the hood motion.

2024 Silverado RST



2024 Sierra Denali EV



2022-2025 Hummer EV Models



NOTE: Manually forcing the hood to open or close can damage the vehicle. Always allow the automatic operation to complete before using the hood again.

Version History

| | |
|-----------------|--|
| Version | 3 |
| Modified | 07/23/2024 - Created on. 08/20/2024- Update name of module to match service terms 09/13/2024- Updated Models. |