

## JLRTB02127NAS2 - ENGINE COOLANT LEVEL LOW MESSAGE DISPLAYED ON INSTRUMENT PANEL

### Customer Voice:

- 'Coolant Level Low' message displayed on the instrument panel cluster,

### Technical Description:

- Permeation of water content from the engine coolant through plastic pipes.

### Status:

- INGENIUM I6 3.0L Petrol, INGENIUM I6 3.0L Petrol PHEV Vehicles Only;
- Remove the fuel supply line (see TOPIx Workshop Manual section 310-01: Fuel Tank and Lines - Removal and Installation - Fuel Supply Line).
- Renew the coolant expansion tank (see TOPIx Workshop Manual section 303-03: Engine Cooling - Removal and Installation - Coolant Expansion Tank)
- Install the new fuel supply line (see TOPIx Workshop Manual section 310-01: Fuel Tank and Lines - Removal and Installation - Fuel Supply Line).
- Check the coolant concentration (see TOPIx Workshop Manual section 303-03: Engine Cooling - General Procedure - Cooling System Concentration Check).

Refer to JLRTB02127NAS2

### Range Rover

- 22MY+ Range Rover
- 23MY+ Range Rover Sport

